


AD-A092 036

NEW YORK STATE DEPT OF ENVIRONMENTAL CONSERVATION ALBANY F/6 13/13  
NATIONAL DAM SAFETY PROGRAM, NANTICOKE CREEK WATERSHED PROJECT --ETC(U)  
SEP 80 G KOCH DACW51-79-C-0001 NL

UNCLASSIFIED

1 to 2  
AD  
A092036



ADA092036

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report Nanticoke Creek Watershed Project, Site 10 Susquehanna River Basin, Broome County, New York Inventory No. 713		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s)	6. PERFORMING ORG. REPORT NUMBER	
George Koch	8. CONTRACT OR GRANT NUMBER(s)	
9. PERFORMING ORGANIZATION NAME AND ADDRESS New York Department of Environmental Conservation 50 Wolf Road Albany, New York		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS New York State Department of Environmental Conservation 50 Wolf Road Albany, NY 12233		12. REPORT DATE 30 September 1980
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report)  UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; Distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES  Original contains color plates: All DTIC reproductions will be in black and white.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability  Nanticoke Creek Broome County Susquehanna River		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)  This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization.  The examination of documents and visual inspection of the Site 10 dam and appurtenant structures did not reveal conditions which constitute a hazard to human life or property.		

DD FORM 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)


DRAFT FILE COPY

8011 19 013

The total discharge capacity of the spillways is adequate for the Probable Maximum Flood (PMF).

The following remedial actions are required during this construction season:

1. Repair the eroded areas on the right cut slope of the right auxiliary spillway, at the downstream end of the left auxiliary spillway, and at the left upstream abutment contact. Reseed as required.
2. Reseed the grass vegetation of the auxiliary spillways (slopes and bottoms) where the previous seeding has not been completely established.
3. Remove the debris on the upstream slope of the earth embankment, and the debris in the downstream channel near the outlet of the right auxiliary spillway.
4. Remove the tree and brush growth observed in both auxiliary spillways at the entrances and exits. Provide a program of periodic cutting and mowing of the embankment and auxiliary spillways.
5. Provide a program of periodic inspection and maintenance of the dam and appurtenances, including yearly operation and lubrication of the reservoir drain system. Document this information for future reference. Also, develop an emergency action plan.



## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Acceptance Date	_____	_____	_____	_____	_____	_____	_____
NTIS No.	_____	_____	_____	_____	_____	_____	_____
DEC ID#	_____	_____	_____	_____	_____	_____	_____
Unannounced	_____	_____	_____	_____	_____	_____	_____
Justification	_____	_____	_____	_____	_____	_____	_____
By _____	_____	_____	_____	_____	_____	_____	_____
District Engineer	_____	_____	_____	_____	_____	_____	_____
Available copies	_____	_____	_____	_____	_____	_____	_____
Special Agent	_____	_____	_____	_____	_____	_____	_____
Dist. Spec. Agent	_____	_____	_____	_____	_____	_____	_____

23  
A

⑪ 31 Sep 88

2  
7/88

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
NANTICOKE CREEK WATERSHED PROJECT  
SITE 10 DAM  
Gover. I.D. No. NY 713  
(DEC. 85D-3946)  
SUSQUEHANNA RIVER BASIN,  
BROOME COUNTY, NEW YORK

TABLE OF CONTENTS

	<u>PAGE NO.</u>
- ASSESSMENT	-
- OVERVIEW PHOTOGRAPH	-
1 PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	2
2 ENGINEERING DATA	4
2.1 GEOLOGY	4
2.2 SUBSURFACE INVESTIGATION	4
2.3 EMBANKMENT AND APPURTENANT STRUCTURES	4
2.4 CONSTRUCTION RECORDS	4
2.5 OPERATION RECORD	4
2.6 EVALUATION OF DATA	5
3 VISUAL INSPECTION	6
3.1 FINDINGS	6
3.2 EVALUATION	7
4 OPERATION AND MAINTENANCE PROCEDURES	8
4.1 PROCEDURES	8
4.2 MAINTENANCE OF THE DAM	8
4.3 WARNING SYSTEM IN EFFECT	8
4.4 EVALUATION	8

29 - 9

	<u>PAGE NO.</u>
5      HYDROLOGIC/HYDRAULIC	9
5.1 DRAINAGE AREA CHARACTERISTICS	9
5.2 ANALYSIS CRITERIA	9
5.3 SPILLWAY CAPACITY	9
5.4 RESERVOIR CAPACITY	9
5.5 FLOODS OF RECORD	9
5.6 OVERTOPPING POTENTIAL	9
5.7 EVALUATION	9
6      STRUCTURAL STABILITY	10
6.1 EVALUATION OF STRUCTURAL STABILITY	10
7      ASSESSMENT/RECOMMENDATIONS	11
7.1 ASSESSMENT	11
7.2 RECOMMENDED MEASURES	11
 <u>APPENDIX</u>	
A.     PHOTOGRAHPS	
B.     ENGINEERING DATA CHECKLIST	
C.     VISUAL INSPECTION CHECKLIST	
D.     HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS	
E.     REFERENCES	
F.     STABILITY ANALYSES	
G.     DRAWINGS	

**PHASE I INSPECTION REPORT**  
**NATIONAL DAM SAFETY PROGRAM**

Name of Dam: Nanticoke Creek Watershed Project, Site 10  
I.D. No. NY 713

State Located: New York

County Located: Broome

Stream: East Branch of Nanticoke Creek  
(tributary of Susquehanna River)

Date of Inspection: July 24, 1980

**ASSESSMENT**

The examination of documents and visual inspection of the Site 10 dam and appurtenant structures did not reveal conditions which constitute a hazard to human life or property.

The total discharge capacity of the spillways is adequate for the Probable Maximum Flood (PMF).

The following remedial actions are required during this construction season:

1. Repair the eroded areas on the right cut slope of the right auxiliary spillway, at the downstream end of the left auxiliary spillway, and at the left upstream abutment contact. Reseed as required.
2. Reseed the grass vegetation of the auxiliary spillways (slopes and bottoms) where the previous seeding has not been completely established.
3. Remove the debris on the upstream slope of the earth embankment, and the debris in the downstream channel near the outlet of the right auxiliary spillway.
4. Remove the tree and brush growth observed in both auxiliary spillways at the entrances and exits. Provide a program of periodic cutting and mowing of the embankment and auxiliary spillways.
5. Provide a program of periodic inspection and maintenance of the dam and appurtenances, including yearly operation and lubrication of the reservoir drain system. Document this information for future reference. Also, develop an emergency action plan.

George Koch

George Koch  
Chief, Dam Safety Section  
New York State Department of  
Environmental Conservation  
NY License No. 45937

Approved By:

Col. W. M. Smith Jr.  
New York District Engineer

Date:

30 Sep'87




Photo #1  
Overview of Nanticoke Site 10

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
NANTICOKE CREEK WATERSHED PROJECT - SITE 10  
I.D. No. NY 713  
D.E.C. #85D-3946  
SUSQUEHANNA RIVER BASIN  
BROOME COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I Inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

Evaluation of the existing conditions of the subject dam to identify deficiencies and hazardous conditions, determine if they constitute hazards to life and property and recommend remedial measures where necessary.

1.2 DESCRIPTION OF PROJECT

a. Description of the Dam and Appurtenant Structures

The Site 10 dam consists of a 540-foot long zoned earth embankment with auxiliary spillways at both ends of the embankment, located in cut sections beyond the abutments of the embankment. The maximum height of the dam is 58 feet. The embankment has a crest width of 19 feet and an upstream slope of 1 vertical on 3 horizontal. The downstream slope is 1 on 2.5. A 10-foot wide bench was constructed in the upstream slope in the vicinity of the principal spillway.

The auxiliary spillways are vegetated earth channels. The left channel has a bottom width of 125 feet, and the right channel is 45 feet wide. Side slopes are 1 on 2.5.

The principal spillway is a rectangular concrete riser which extends above the upstream slope near its toe. The riser is topped by a triangular trash rack, the sides of which form a drop inlet, which is utilized during high reservoir levels. Under low flow conditions, a 12 inch by 2 feet 7 inch rectangular low stage inlet in the upstream side of the riser controls the reservoir level.

A 42-inch diameter reinforced concrete pipe controls the flow between the riser and the impact basin located at the toe of the dam. A 16-inch diameter cast-iron pipe, with a manually operated slide gate, the controls of which are located atop the riser, serve as the reservoir drain system.

b. Location

The dam is located on the East Branch of Nanticoke Creek a tributary of the Susquehanna River, approximately 2.5 miles northeast of the Village of Nanticoke.

c. Size Classification

The dam is 58 feet high and is classified as "intermediate" in size (40 to 100 feet in height).

d. Hazard Classification

The dam is classified as high hazard, because of its location above the homes along County Route #26.

e. Ownership

The dam is owned and operated by the County of Broome, New York.

f. Purpose of the Dam

The dam is a flood water retarding structure.

g. Design and Construction History

The dam was designed by the U.S. Department of Agriculture, Soil Conservation Service (SCS). Construction of the dam was completed in 1979. The SCS office for Broome County, located at the Broome County Airport, has all design and construction information.

h. Normal Operating Procedures

Normal flows are discharged through the principal spillway. This structure has sufficient capacity to store and discharge a 100-year flood without use of the auxiliary spillways. Flow in excess of the 100-year storm will be discharged through the auxiliary spillways.

**1.3 PERTINENT DATA**

a. <u>Drainage Area (sq. mi.)</u>	4.5
b. <u>Discharging at Dam (cfs)</u>	
Principal spillway at maximum high water	320
Principal spillway at auxiliary spillway crest elev.	300
Reservoir drain to principal spillway crest elev.	25
Total spillway capacity at maximum high water	11,546
c. <u>Elevation (USGS Datum)</u>	
Top of dam	1134.6
Auxiliary spillway crest	1127.0
Principal spillway crest	1112.9
Low stage inlet, invert elev.	1092.6
Reservoir drain, invert elev.	1081.0

<u>d. Reservoir (Acres)</u>		
Surface area at top of dam	42	
Surface area at crest of auxiliary spillway	33	
Surface area at crest of principal spillway	20	
<u>e. Storage Capacity (Acre-Feet)</u>		
Top of dam	899	
Auxiliary spillway crest	618	
Principal spillway crest	242	
<u>f. Dam</u>		
Embankment type:	homogeneous with keyed earth cutoff trench and drain parallel to axis of dam.	
Embankment length (ft.)	520	
Slopes	upstream	1 vertical on 3 horizontal
	downstream	1 vertical on 2.5 horizontal
Crest width (ft.)		19
<u>g. Principal Spillway</u>		
Type:	Uncontrolled, reinforced concrete 2 stage drop inlet (3.5 x 10.5 ft.) rising 35.0 feet above the 42-inch diameter reinforced concrete pipe invert; length of pipe 298. feet; rip rapped plunge pool.	
Weir length (ft.)		21
<u>h. Auxiliary Spillway (Emergency)</u>		
Type:	Two grass-lined channels having trapezoidal cross sections.	
Bottom width (ft.)		
Eastern channel	210	
Western channel	100	
Side slopes (vert.:horiz.)		1:2.5
Length of level section (in profile) (ft.)	50	
Exit slope (ft/ft)	0.025	
<u>i. Reservoir Drain</u>		
Type:	16-inch diameter cast-iron pipe with reinforced concrete inlet.	
Control:	Manually operated vertical slide gate mounted along the inside of the principal spillway riser.	

## SECTION 2: ENGINEERING DATA

### 2.1 GEOLOGY

The Nanticoke Creek Watershed Project Dam No. 10 is located in the glaciated portion of the "Appalachian Uplands" (northern extreme of the Appalachian Plateau) physiographic province of New York State. These uplands were formed by dissection of the uplifted but flat lying sandstones and shales of the middle and upper Devonian Catskill Delta. The plateau surface is represented by flat-topped divides with drainage generally southwest toward the Susquehanna River system.

Glacial cover is generally thin, although some north-south valleys are so thick that they are completely buried. The present surficial deposits have resulted primarily from glaciations during the Cenozoic Era, the last of which was the Wisconsin glaciation, approximately 11,000 years ago.

### 2.2 SUBSURFACE INVESTIGATION

A subsurface investigation was conducted by the Soil Conservation Service in 1970. This program consisted of 21 drill holes and 20 test pits at locations along the dam, auxiliary spillways, structural elements, and borrow area. Applicable subsurface information is included in Appendix F.

In general, the soils in the vicinity of the dam are of glacial till or glacial lacustrine origin, and are silty gravel, clayey gravels, and sandy silts over shale bedrock. The permeability of these soils is low.

### 2.3 EMBANKMENT AND APPURTENANT STRUCTURES

The dam was designed and constructed under the supervision of the Soil Conservation Service. "As-Built" drawings of this dam are on file at the SCS office in Broome County. Selected drawings of the dam and appurtenances are included in Appendix F. The dam is composed of zoned earth fill, the maximum height of which is 58 feet, a 22 foot wide cut-off trench having side slopes of 1 on 2, and a foundation drain parallel to the axis of the dam approximately 100 feet downstream from the centerline. A reinforced concrete riser serves as the principal spillway and 2 vegetated channels serve as auxiliary spillways.

### 2.4 CONSTRUCTION RECORDS

Complete construction records are available from the SCS office in Broome County. No major construction changes were instituted.

### 2.5 OPERATION RECORD

Since the dam is an ungated floodwater retarding structure, no operating records are maintained regarding water levels. During periods of extreme rainfall, SCS personnel do monitor the reservoir.

## **2.6 EVALUATION OF DATA**

The data presented in this report has been compiled from information obtained from Mr. Gary Page, Project Engineer for SCS in Broome County, and Mr. Donald Lake, Head of the SCS Design Section in Syracuse, New York. This information appears to be adequate and reliable for Phase I Inspection purposes.

### SECTION 3: VISUAL INSPECTION

#### 3.1 FINDINGS

##### a. General

Visual inspection of Dam 10 was conducted on July 24, 1980. The weather was cloudy and the temperature ranged in the 80's. The water surface was approximating the invert of the low stage inlet on the principal spillway riser.

##### b. Embankment

No signs of distress were observed in the earth embankment, and no evidence of seepage, misalignment, sloughing, subsidence, depressions, surface cracking, or undesirable growth were noted in connection with the embankment. While no riprap was in use on the upstream slope for wave protection, little erosion was apparent. Slight erosion was observed at the left upstream abutment contact. The maximum depth of erosion was 6 inches and extended from the waterline approximately 50 feet up the abutment contact. Some debris was observed on the upstream slope approximately one-third up the slope and appeared to result from a previous storm.

An internal drainage system composed of 2-10 inch diameter pipes surrounded by "drain fill" and extending parallel to the axis of the dam provide drainage at the embankment-subgrade contact. These pipes exit through the concrete walls of the impact basin. No discharge was apparent from these pipes.

##### c. Principal Spillway

The principal spillway consists of a vertical drop inlet structure, a reinforced concrete pipe through the embankment, a plunge pool at the toe of the embankment, and an outlet channel. These components appear to be in satisfactory condition.

##### d. Auxiliary Spillways

The two vegetated auxiliary spillways in earth cut sections are located near the abutments of the embankment. The following problem areas were observed:

1. Both channels require mowing of vegetative growth and removal of the trees at the entrance and exit of both auxiliary spillways.
2. The side slopes of the auxiliary spillway channels have not completely established vegetation. Erosion of the left cut slope was noted above a rock cut near the entrance of the right auxiliary spillway. In addition, a zone of seepage (from the adjacent hillside) has caused sloughing and erosion at the downstream end of the right slope of the right auxiliary spillway. Runoff from the left hillside has eroded the outlet end of the left auxiliary spillway.

##### e. Reservoir Drain

The 12-inch diameter reservoir drain and manually operated slide gate may be used to lower the reservoir. The slide gate control mechanism is located at the top of the riser. This system is reported to be operational.

f. Downstream Channel

The downstream channel below the plunge pool is riprapped and joins the original Nanticoke Creek channel near the outlet. The channel appears to be stable in the near vicinity of the dam. Some debris was noted in the channel resulting from erosion of a side channel stream near the outlet of the right auxiliary spillway.

g. Reservoir

There are no visible signs of instability or sedimentation problems within the reservoir area.

3.2 EVALUATION

The problem areas observed during the inspection are considered minor in nature, requiring only limited remedial action. The required remedial action is as follows:

1. Erosion observed at the downstream end of the left auxiliary spillway, and on the right side of the right auxiliary spillway (above the rock cut, and at the outlet end) requires repair and reseeding.
2. The grass vegetation has not established itself properly in many areas (particularly on the slopes and bottoms of the auxiliary spillways) and requires reseeding.
3. Slight erosion was noted at the left upstream abutment contact. This area requires repair and reseeding.
4. Debris on the upstream slope of the embankment should be removed.
5. Debris in the downstream channel, from a side channel stream, requires removal.
6. Extensive vegetation was observed in both auxiliary spillways at each end. This vegetation must be removed. Provide a program of periodic cutting and mowing of the embankment and auxiliary spillway surfaces.
7. Provide a program of periodic inspection and maintenance of the dam and appurtenances, including yearly operation and lubrication of the reservoir drain system. Document this information for future reference. Also develop an emergency action plan.

## SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

### 4.1 PROCEDURES

The normal water surface elevation is approximated by the low stage inlet elevation. Downstream flows are limited by the 42-inch diameter principal spillway pipe, except during extremely heavy runoff when the auxiliary spillways are in service. The dam provides 590 acre feet of flood storage between normal water level and the crest of the auxiliary spillways.

### 4.2 MAINTENANCE OF THE DAM

The dam is maintained by the County of Broome, New York. Maintenance is considered satisfactory.

### 4.3 WARNING SYSTEM IN EFFECT

There is no warning system in effect or in preparation.

### 4.4 EVALUATION

The dam and appurtenant structures have been maintained in a satisfactory condition.

## SECTION 5: HYDRAULIC/HYDROLOGIC

### 5.1 DRAINAGE AREA CHARACTERISTICS

The Nanticoke Creek Dam Site 10 is located on an unnamed tributary of the East Branch of the Nanticoke, Susquehanna River Basin. The drainage area contributing to the site is 4.53 square miles. The watershed consists of woodlands and fields in a rural location. Relief ranges from moderate to steep.

### 5.2 ANALYSIS CRITERIA

The analysis of the spillway capacity of the dam and storage of the reservoir was performed using the Corps of Engineers HEC-1 computer model. The unit hydrograph was defined by the Snyder Synthetic Unit Hydrograph method and the Modified Puls routing procedure was incorporated. The Probable Maximum Precipitation (PMP) used was 21.0 inches (24 hrs., 200 sq. mi.) from Hydrometeorological Report No. 33. Several floods were selected (%'s PMF) for analysis in accordance with recommended guidelines of the Corps of Engineers. The PMF inflow of 7404. cfs, was routed through the reservoir and the peak outflow was determined to be 7367 cfs.

### 5.3 SPILLWAY CAPACITY

The service spillway consists of a 3.5 x 10.5 feet drop inlet structure (21' weir length) emptying into a 42 inch diameter reinforced concrete pipe. A riprap lined plunge pool is located at the toe of the dam for energy dissipation. The capacities at emergency spillway crest and top of dam are 300. cfs and 520 cfs respectively. The emergency spillway consists of two grass lined trapezoidal channels, one on either abutment. The left channel has a bottom width of 125 feet and the right has a bottom width of 45 feet. At top of dam they bring the total discharge capacity to 11,546 cfs.

### 5.4 RESERVOIR CAPACITY

The reservoir capacities at the crest of the spillway, and at the top of dam are 242 and 399 acre feet respectively. Surcharge storage, spillway crest to top of dam, is 657 acre feet or an equivalent runoff of 2.72 inches.

### 5.5 FLOODS OF RECORD

At the time of inspection the water surface elevation had not yet reached the crest of the riser.

### 5.6 OVERTOPPING POTENTIAL

The maximum capacity of the spillways is 11,546 cfs before overtopping of the dam would occur. This capacity results in the ability to pass the full PMF of 7404 cfs, and greatly attenuate storms of lesser magnitude.

### 5.7 EVALUATION

The spillway is adequate to pass the full PMF, with approximately 2 feet of freeboard.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

#### a. Visual Observations

No signs of distress were observed in connection with the earth embankment.

#### b. Design and Construction Data

A stability analysis was conducted by SCS during the design of the dam. The analyses were performed using the modified swedish circle method. The soil parameters assumed were  $\gamma = 119 \text{ & } 132$ ,  $\gamma_{sub} = 56.5 \text{ & } 69.5$ ,  $\phi = 24^{\circ}$  &  $25^{\circ}$ ,  $c = 850$  and  $825$ . The results of the stability analyses area as follows:

<u>Condition</u>	<u>Minimum Factor of Safety</u>
1. Upstream slope = 1:3, full drawdown no berm	1.63
2. Downstream slope = 1:2.5, steady state condition, no berm	1.92

The calculated factors of safety for this dam are in excess of the minimum factors recommended by the Corps of Engineers. The dam is, therefore, considered to have adequate factors of safety for stability.

A summary of the analysis is included in Appendix E.

#### c. Post Construction Changes

No post construction changes were instituted.

#### d. Seismic Stability

The dam is Located in Seismic Zone 1. Therefore, a seismic analysis is not warrented.

## SECTION 7: ASSESSMENT/RECOMMENDATIONS

### 7.1 ASSESSMENT

#### a. Safety

The Phase I Inspection of the Nanticoke Creek Dam Site 10 did not reveal conditions which constitute a hazard to human life or property. The earth embankment is not considered to be unstable and appears capable of retarding floodwaters resulting from the PMF.

#### b. Adequacy of Information

Information reviewed for Phase I Inspection purposes is considered adequate.

#### c. Need for Additional Investigations

No additional investigations are required at this time.

### 7.2 RECOMMENDED MEASURES

1. Repair the eroded areas on the right cut slope of the right auxiliary spillway, at the downstream end of the left auxiliary spillway, and at the left upstream abutment contact. Reseed as required.
2. Reseed the grass vegetation of the auxiliary spillways (slopes and bottoms) where the previous seeding has not been completely established.
3. Remove the debris on the upstream slope of the earth embankment, and the debris in the downstream channel near the outlet of the right auxiliary spillway.
4. Remove the tree and brush growth observed in both auxiliary spillways at the entrances and exits. Provide a program of periodic cutting and mowing of the embankment and auxiliary spillways.
5. Provide a program of periodic inspection and maintenance of the dam and appurtenances, including yearly operation and lubrication of the reservoir drain system. Document this information for future reference. Also, develop an emergency action plan for notification of residents and proper authorities in the event of hazardous conditions.

**APPENDIX A**

**PHOTOGRAPHS**




Photo #2  
Upstream Face



Photo #3  
Plunge Pool & Downstream Channel




Photo #4  
Right Auxiliary Spillway



Photo #5  
Left Auxiliary Spillway



Photo #6  
Erosion at Outlet of Left  
Auxiliary Spillway

APPENDIX B

VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam Nanticoke S.No 10

Fed. I.D. # NY 713 DEC Dam No. 85 D - 3946

River Basin Susquehanna

Location: Town Nanticoke County Broome

Stream Name trib. of E. Branch Nanticoke CK

Tributary of Susquehanna

Latitude (N) 42° 17' Longitude (W) 76° 0.5'

Type of Dam Zoned earth

Hazard Category "C"

Date(s) of Inspection July 24, 1980

Weather Conditions Cloudy 80's

Reservoir Level at Time of Inspection approx. at low stage elev.

b. Inspection Personnel J.C. Vitch, R.P. McCarty

c. Persons Contacted (Including Address & Phone No.)

Cary Page - SCS Broome County Airport

Donald Lake - SCS Syracuse

d. History:

Date Constructed 1979 Date(s) Reconstructed  

Designer SCS

Constructed By Bestway Construction Inc. Endicott N.Y.  
Earth set: Howes, Jones Construction Co. Appalachia N.Y.

Owner Broome County, N.Y.

2) Embankment

a. Characteristics

- (1) Embankment Material Glacial till
- (2) Cutoff Type Earth
- (3) Impervious Core Zoned embankment
- (4) Internal Drainage System standard SCS design w/  
perforated pipes surrounded by drain fill material
- (5) Miscellaneous \_\_\_\_\_

b. Crest

- (1) Vertical Alignment good
- (2) Horizontal Alignment good
- (3) Surface Cracks none
- (4) Miscellaneous \_\_\_\_\_

c. Upstream Slope

- (1) Slope (Estimate) (V:H) 1:3
- (2) Undesirable Growth or Debris, Animal Burrows \_\_\_\_\_  
some debris & stone on slope from per' station
- (3) Sloughing, Subsidence or Depressions \_\_\_\_\_  
none

(4) Slope Protection none

---

(5) Surface Cracks or Movement at Toe unobservable

---

d. Downstream Slope

(1) Slope (Estimate - V:H) 2.5

(2) Undesirable Growth or Debris, Animal Burrows \_\_\_\_\_

(3) Sloughing, Subsidence or Depressions \_\_\_\_\_

name

(II) Surface Cracks or Movement at Toe \_\_\_\_\_

None

(5) See page one

---

— 1 —

(6) External Drainage System (Ditches, Trenches; Blanket) \_\_\_\_\_

ripened at about 20° C.

(7) Condition Around Outlet Structure \_\_\_\_\_

good

(8) Seepage Beyond Toe none dry

---

Journal of Health Politics, Policy and Law, Vol. 35, No. 4, December 2010  
DOI 10.1215/03616878-35-4 © 2010 by The University of Chicago

e. Abutments - Embankment Contact

(1) Erosion at Contact left upstream contact is max.  
6' erosion depth from water line = 50' up slope

(2) Seepage Along Contact \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

3) Drainage System

a. Description of System 2 - 10" diam pipes  
surrounded by drain fill material  
line parallel to axis of dam & extends along service  
(spillway) pipe

b. Condition of System appears good

c. Discharge from Drainage System none  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.)

none  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

5) Reservoir

a. Slopes good

b. Sedimentation none reported

c. Unusual Conditions Which Affect Dam \_\_\_\_\_

6) Area Downstream of Dam

a. Downstream Hazard (No. of Homes, Highways, etc.)

houses along, no st & u 26

b. Seepage, Unusual Growth

none

c. Evidence of Movement Beyond Toe of Dam

none

d. Condition of Downstream Channel some debris (stone) in channel right side from stream at outlet of rt. auxiliary

7) Spillway(s) (Including Discharge Conveyance Channel)

a. General Service sp. way under dam - river

42" concrete pipe & inlet basin

2 vegetated earth channels at abutts

b. Condition of Service Spillway

good

c. Condition of Auxiliary Spillway traps in both ends of  
both auxiliaries vegetation not established at all locations  
downstream end crevices of left aux from hillside runoff  
right cut slope of rt. aux. sloughed downcut at outlet  
from nearby springs on hillside - also above rock cut

d. Condition of Discharge Conveyance Channel \_\_\_\_\_

generally good

8) Reservoir Drain/Outlet

Type: Pipe  Conduit  Other

Material: Concrete  Metal  Other

Size: 16" Length \_\_\_\_\_

Invert Elevations: Entrance \_\_\_\_\_ Exit \_\_\_\_\_

Physical Condition (Describe): Unobservable

Material: \_\_\_\_\_

Joints: \_\_\_\_\_ Alignment \_\_\_\_\_

Structural Integrity: \_\_\_\_\_

Hydraulic Capability: \_\_\_\_\_

Means of Control: Gate  Valve  Uncontrolled

Operation: Operable  Inoperable  Other

Present Condition (Describe): good condition

9) Structural

- a. Concrete Surfaces good cond'ion
- b. Structural Cracking none evident
- c. Movement - Horizontal & Vertical Alignment (Settlement)  
none evident
- d. Junctions with Abutments or Embankments  
good cond'ion
- e. Drains - Foundation, Joint, Face  
junction drains junction
- f. Water Passages, Conduits, Sluices  
good cond'ion
- g. Seepage or Leakage none evident

h. Joints - Construction, etc. \_\_\_\_\_

good condition

\_\_\_\_\_

\_\_\_\_\_

i. Foundation unobservable

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

j. Abutments n/a

\_\_\_\_\_

\_\_\_\_\_

k. Control Gates operable

\_\_\_\_\_

\_\_\_\_\_

l. Approach & Outlet Channels n/a

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

m. Energy Dissipators (Plunge Pool, etc.)

plunge pool ripraped - good condition

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

o. Stability appears adequate

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

APPENDIX C

HYDROLOGIC / HYDRAULIC

ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS  
HYDROLOGIC AND HYDRAULIC  
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	Elevation (ft.)	Surface Area (acres)	Storage Capacity (acre-ft.)
1) Top of Dam	<u>111.6</u>	<u>41.8</u>	<u>845.5</u>
2) Design High Water (Max. Design Pool)	<u>1130.9</u>	<u>36.9</u>	<u>731.5</u>
3) Auxiliary Spillway Crest	<u>1127.0</u>	<u>33.3</u>	<u>618.0</u>
4) Pool Level with Flashboards	<u>-</u>	<u>-</u>	<u>-</u>
5) Service Spillway Crest	<u>1112.9</u>	<u>19.8</u>	<u>291.8</u>

DISCHARGES

	Volume (cfs)
1) Average Daily	<u>5.</u>
2) Spillway @ Maximum High Water (Tot v.)	<u>11,596.</u>
3) Spillway @ Design High Water v.	<u>4,967.</u>
4) Spillway @ Auxiliary Spillway Crest Elevation	<u>301.</u>
5) Low Level Outlet	<u>50</u>
6) Total (of all facilities) @ Maximum High Water	<u>11,646.</u>
7) Maximum Known Flood	<u>— Not to second stage.</u>
8) At Time of Inspection	<u>1.</u>

CREST:

ELEVATION: 1134.6Type: ZONED COMPACTED EARTH FILLWidth: 18' Length: 530'Spillover PARK PLATE SERVICE, Velocity 6.0 ft/s. (2)Location Service embankment, left & right ACOT

SPILLWAY:

SERVICE	AUXILIARY
<u>1115.7</u>	<u>1127.0</u>
<u>18' width (K.C.)</u>	Type <u>Open Channel (2)</u>
<u>1' wall height</u>	Width <u>190 mm</u>
<u>Type of Control</u>	
<u>✓</u>	Uncontrolled <u>✓</u>
Controlled:	
<u>—</u>	<u>—</u>
Type (Flashboards; gate)	
Number	
Size/Length	
Invert Material	<u>Asphalt</u>
Anticipated Length of operating service	<u>50 ft.</u>
<u>100' condent</u>	Chute Length
<u>3' V</u>	Height Between Spillway Crest & Approach Channel Invert (Weir Flow)
	<u>2.1 ft.</u>

HYDROMETEROLOGICAL GAGES:

Type : \_\_\_\_\_

Location: \_\_\_\_\_

Records:

Date - \_\_\_\_\_

Max. Reading - \_\_\_\_\_

FLOOD WATER CONTROL SYSTEM:

Warning System: None

Method of Controlled Releases (mechanisms):

ATTACHMENT RELEASING Device

DRAINAGE AREA: 4.53 mi<sup>2</sup>

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: Rural Residential / mixed

Terrain - Relief: Flat / gentle

Surface - Soil: Loamy soil -

Runoff Potential (existing or planned extensive alterations to existing  
(surface or subsurface conditions)

High runoff potential - Slopes & impervious.

Potential Sedimentation problem areas (natural or man-made; present or future)

None

Potential Backwater problem areas for levels at maximum storage capacity  
including surcharge storage:

None

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the  
Reservoir perimeter:

Location: None

Elevation: \_\_\_\_\_

Reservoir:

Length @ Maximum Pool 1600 (Miles)

Length of Shoreline (@ Spillway Crest) 1600 (Miles)

PANTHERS, 100, BENT WING.

200 - 100 = 100

$$A = \pi r^2 \text{ miles} = \pi (15)^2 \text{ mi}^2$$

$$\begin{aligned}f_1 &= 4.7 \quad \text{Time} = 1.13 \text{ min} \\f_2 &= 4.7 \text{ (avg)} \quad \text{Time} = 1.15 \text{ hr} \\f_3 &= 0.63 \quad * \\T_p &= t_2 + 5h = 3.75 \text{ hrs.}\end{aligned}$$

201070	201070 (2010)	201070 (2010)
1000	0	0
1000	34	0
1000	50	50
1000	60	20
1000	7	287
1000	0	1176

Carson

\*\*\*\*\*  
 FLUD METERGRAPH PACKAGE (MEC-1)  
 DAM SIGHTY VERSION: JULY 1978  
 LAST MODIFICATION: 26 FEB 79  
 MODIFIED FOR HONEYWELL APR 79  
 \*\*\*\*\*  
 1 A1 HANTICKE CREEK SITE 10  
 . 2 A2 PHASE 1  
 . 3 A3 PWF  
 . 4 B 20C 0 15 0 0 0 0 C C 0 0 0  
 . 5 B1 5  
 . 6 J 1 6 1  
 . 7 J1 .2 .4 .5 .6 .8 1  
 . 8 K C 1 2 1  
 . 9 K1 INFLOW FROM BASIN  
 . 10 H 1 1 .53  
 . 11 P 21.0 111 123 133 142 1 .1  
 . 12 T  
 . 13 W 3.75 .625  
 . 14 X -.2.C -.05 1  
 . 15 K 1 1 2 1  
 . 16 K1 ROUTE THROUGH RESERVOIR  
 . 17 Y  
 . 18 Y1 1  
 . 19 Y41C92.6 1112.9 1127.0 1130.4 1134.6  
 . 20 Y5 55 301 2967 11546  
 . 21 \$5 28 242 618 735 899  
 . 22 SE 1C77 1092.6 1112.9 1127.0 1130.4 1134.6  
 . 23 \$51112.9  
 . 24 \$51134.6 2.7 1.5 520  
 . 25 K 99

\*\*\*\*\*  
 NEW YORK STATE  
 DEPT OF ENVIRONMENTAL CONSERVATION  
 FLDC PROTECTION BUREAU  
 \*\*\*\*\*

PREVIOUS IF SEQUENCE OF STREAM NETWORK CALCULATIONS  
ROUTE HYDROGRAPH AT  
ROUTE HYDROGRAPH TO  
END OF NETWORK

FLUCU HYDROGRAPH PACKAGE (MFC-1)  
CAN SAFETY VERSION: JULY 1973  
LAST MODIFICATION: 26 FEB 79  
MODIFIED FOR MC-EVANLL Apo 79

RUN DATE 06/08/80 HANTICKE CREEK SITE 10  
PHASE I  
PRF

AC	MR	MY	IDAY	JHR	IWHR	METRC	IPLT	IPAT	ISTAN
200	0	15	C	0	0	C	0	0	0
				JOPT	WT	TRACE			
				5	0	C			

MULTI-PLAIN ANALYSES TO BE PERFORMED  
NPLAN= 1 RTIC= 6 LRTD= 1  
RTIC= 0.20 0.40 0.50 0.60 0.80 1.00

\*\*\*\*\*

#### SUB-AREA RUNOFF COMPUTATION

INFLOK FROM BASIN  
1STAQ 1C0MP 1ECON 1TAPE 1PLT 1PAT 1NAME 1STAGE 1AUTG  
1 1 4.53 0. 4.53 0. 0. 0. 0. 0.

IMDCC	1UMG	TAREA	SNAP	HYDROGRAPH DATA	ISNUC	ISNAME	LOCAL
1	1	4.53	0.	TRSDA TRSPC RATIC 0.	0.	0	0

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.	21.00	111.00	123.00	133.00	142.00	C.	0.

TRSPC COMPUTED BY THE PROGRAM IS 0.60C

LADPT	STRKA	DTRK	RTIDL	ERAIN	LOSS DATA	STRTL	CNSTL	ALSMX	RTIMP
0	C.	0.	1.00	0.	0.	1.00	0.10	0.	C.

UNIT HYDROGRAPH DATA  
TP= 3.075 CP=0.63 NTAB= C

RECEDITION DATA  
STRQ= -2.00 QCSN= -0.05 RTICR= 1.00  
FROM GIVEN STRYER CP AND TP ARE TC=16.37 AND RT=14.00 INTERVALS

UNIT HYDROGRAPH	END-OF-PERIOD ODOTATES	LAG	3.073 HOURS	CP= C.62	VOL= 1.00
9. 32. 66. 106. 157. 197. 246. 257. 346. 354.	422. 461. 483. 497. 502. 497. 475. 475. 445. 415.	367. 415. 445. 445. 445. 445. 415. 415. 415. 387.			
300. 235. 312. 291. 271. 252. 235. 235. 219. 156.	177. 165. 153. 143. 133. 124. 115. 115. 107. 92.	177. 165. 153. 143. 133. 124. 115. 115. 107. 92.			
87. 81. 75. 70. 65. 61. 57. 53. 49. 46.	43. 4C. 37. 34. 32. 30. 28. 24. 22. 21.	43. 4C. 37. 34. 32. 30. 28. 24. 22. 21.			
21. 19. 18. 17. 16. 15. 14. 13. 12. 11.	10. 1C. 9. 8. 7. 6. 5. 4. 3. 2.	10. 1C. 9. 8. 7. 6. 5. 4. 3. 2.			



	PEAK	6-HCUP	24-HCUP	72-HCUP	TOTAL VOLUME
CFS	7404.	5966.	2208.	1075.	24579.
CMS	210.	169.	63.	36.	6050.
INCHES					
MM	311.18	12.25	18.13	18.40	18.40
AC-FT			460.63	467.43	467.43
TRDLS CUM	2958.	3649.	4379.	4444.	4444.
			5402.	5481.	2481.

DAVF\*

## STATION 1

INFLUW(\*), OUTFLOW(\*) AND OBSERVED FLOW(500).

2000, 4000, 6000.

C<sub>1</sub>, C<sub>2</sub>, C<sub>3</sub>

PRECIP(L) AND EXCESS(X) C<sub>1</sub>, C<sub>2</sub>, C<sub>3</sub>

0. 1.00 2.00 3.00 4.00 5.00 6.00 7.00 8.00 9.00 10.00 11.00 12.00 13.00 14.00 15.00 16.00 17.00 18.00 19.00 20.00 21.00 22.00 23.00 24.00 25.00 26.00 27.00 28.00 29.00 30.00 31.00 32.00 33.00 34.00 35.00 36.00 37.00 38.00 39.00 40.00 41.00 42.00 43.00 44.00 45.00 46.00 47.00 48.00 49.00 50.00 51.00 52.00 53.00 54.00 55.00 56.00 57.00 58.00 59.00 60.00 61.00 62.00 63.00 64.00 65.00 66.00 67.00 68.00 69.00 70.00 71.00 72.00 73.00 74.00 75.00 76.00 77.00 78.00 79.00 80.00 81.00 82.00 83.00 84.00 85.00 86.00 87.00 88.00 89.00 90.00 91.00 92.00 93.00 94.00 95.00 96.00 97.00 98.00 99.00 100.00

14.30	561
14.45	571
15.00	611
15.15	211
15.30	621
15.45	531
17.00	681
17.15	691
17.30	701
17.45	711
18.00	721
18.15	731
18.30	741
19.45	751
19.60	761
19.75	771
19.90	781
19.45	791
20.00	701
20.15	811
20.30	821
20.45	831
21.00	841
21.15	851
21.30	861
21.45	871
22.00	881
22.15	891
22.30	901
22.45	911
22.60	921
23.15	931
23.30	941
23.45	951
0.	961
0.15	971
0.30	981
0.45	991
1.00	101
1.15	101
1.30	1021
1.45	1031
2.00	1041
2.15	1051
2.30	1061
2.45	1071
4.00	1121
4.45	1111
5.30	1181
5.45	1191
6.00	1201
6.15	1211

8.451241  
7.601241  
7.151251  
7.301261  
7.451271  
8.001281  
8.151291  
8.301301  
8.451311  
9.001321  
9.151331  
9.301341  
9.451351  
10.001361  
10.151371  
10.301381  
10.451391  
11.001401  
11.151411  
11.301421  
11.451431  
12.001441  
12.151451  
12.301461  
12.451471  
13.001481  
13.151491  
13.301501  
13.451511  
14.001521  
14.151531  
14.301541  
14.451551  
15.001561  
15.151571  
15.301581  
15.451591  
16.001601  
16.151611  
16.301621  
16.451631  
17.001641  
17.151651  
17.301661  
17.451671  
18.001681  
18.151691  
18.301701  
18.451711  
19.001721  
19.151731  
19.301741  
19.451751  
20.001761  
20.151771  
20.301781  
20.451791  
21.001791  
21.151801  
21.301821  
21.451831  
22.001841  
22.151851  
22.301861  
22.451871

23.30198  
23.60191  
0.0192.  
0.15193.  
0.30194.  
0.45195.  
1.00196.  
1.15197.  
1.30198.  
1.45199.  
2.00200.

STATION 1, PLAN 1, PATIC 3  
END-OF-PERIOD HYDROGRAPH CRIMINATES

	OUTFLOW	STORAGE	STAGE
55.	54.	230.	1112.3
52.	52.	231.	1112.2
50.	49.	232.	1112.1
47.	47.	233.	1112.0
45.	45.	224.	1111.9
43.	43.	225.	1111.8
41.	41.	226.	1111.7
40.	39.	227.	1111.6
40.	40.	236.	1111.5
40.	40.	237.	1111.4
39.	39.	228.	1111.3
38.	38.	229.	1111.2
38.	38.	217.	1111.1
37.	37.	218.	1111.0
37.	38.	219.	1110.9
37.	38.	210.	1110.8
36.	45.	211.	1110.7
57.	62.	212.	1110.6
171.	193.	213.	1110.5
3343.	3656.	214.	1110.4
2920.	2694.	215.	1110.3
2610.	2557.	216.	1110.2
1539.	1341.	217.	1110.1
1644.	1349.	218.	1110.0
	1264.	2273.	1109.9
	1134.	2134.	1109.8
	1029.	2061.	1109.7
	912.	1973.	1109.6
		1029.	1109.5
		912.	1109.4
		818C.	1109.3
		3C27.	1109.2
		2572.	1109.1
		2164.	1109.0
		2161.	1108.9
		196.	1108.8
		186.	1108.7
		176.	1108.6
		166.	1108.5
		156.	1108.4
		146.	1108.3
		136.	1108.2
		126.	1108.1
		116.	1108.0
		106.	1107.9
		96.	1107.8
		86.	1107.7
		76.	1107.6
		66.	1107.5
		56.	1107.4
		46.	1107.3
		36.	1107.2
		26.	1107.1
		16.	1107.0
		6.	1106.9
		0.	1106.8

1166.4	1176.2	1176.6	1176.9	1107.1	1107.4	1107.0	1107.4	1107.4
1168.5	1178.9	1179.2	1179.6	1110.0	1110.4	1110.8	1111.3	1111.8
1170.6	1180.8	1181.3	1181.7	1114.1	1114.6	1115.2	1115.5	1116.5
1171.6	1182.3	1182.3	1182.3	1123.1	1125.6	1127.3	1128.5	1129.9
1173.0	1183.4	1183.7	1183.7	1130.7	1130.7	1131.7	1132.6	1133.9
1174.6	1184.7	1185.0	1185.7	1130.7	1130.7	1131.7	1132.6	1133.9
1176.7	1186.0	1186.0	1186.9	1107.1	1107.4	1107.0	1107.4	1107.4
1178.6	1188.5	1189.2	1189.6	1110.0	1110.4	1110.8	1111.3	1111.8
1180.2	1190.8	1191.3	1191.7	1114.1	1114.6	1115.2	1115.5	1116.5
1181.3	1192.3	1192.3	1192.3	1123.1	1125.6	1127.3	1128.5	1129.9
1182.3	1193.4	1193.7	1193.7	1130.7	1130.7	1131.7	1132.6	1133.9
1183.4	1194.7	1195.0	1195.7	1130.7	1130.7	1131.7	1132.6	1133.9
1184.7	1196.0	1196.0	1196.9	1107.1	1107.4	1107.0	1107.4	1107.4

PEAK OUTFLD. IS 3678. AT TIME 43:50 HOURS

	PEAK	6-HRUF	24-HRUF	72-HRUF	TOTAL VELLIE
CFS	3675.	2794.	669.	440.	8795.
CMS	104.	79.	25.	12.	2452.
INCHES		5.74	7.14	7.93	7.53
MM		145.74	181.32	191.24	191.24
AC-FT		1386.	1724.	1616.	1616.
TRDS CU M		1709.	2126.	2243.	2243.



15.00	60110
15.12	6110
15.30	6210
15.42	6310
16.09	5410
16.15	6510
16.30	6610
16.43	6710
17.00	6810
17.15	6910
17.30	7010
17.45	7110
18.00	7210
18.15	7310
18.30	7410
18.45	7510
19.00	7610
19.15	7710
19.30	7810
19.45	7910
20.00	8010
20.15	8110
20.30	8210
20.45	8310
21.00	8410
21.15	8510
21.30	8610
21.45	8710
22.00	8810
22.15	8910
22.30	9010
22.45	9110
23.00	9210
23.15	9310
23.30	9410
23.45	9510
00	9610
0125	9710
0330	9810
0445	9910
100016010	10016010
11511110	11511110
13011210	13011210
14511310	14511310
20011410	20011410
21511510	21511510
23311610	23311610
24511710	24511710
30011810	30011810
31511910	31511910
33011010	33011010
34511110	34511110
40011210	40011210
41511310	41511310
43011410	43011410
44511510	44511510
50011610	50011610
51511710	51511710
53011810	53011810
54511910	54511910
60012010	60012010
61512110	61512110
63012210	63012210
64512310	64512310

7.301251  
7.451271  
8.001241  
8.151291  
8.301311  
8.4513101  
9.0013201  
9.1513301  
9.3013401  
9.4513501  
10.0013601  
10.1513701  
10.3013801  
10.4513901  
11.0014001  
11.1514101  
11.3014201  
11.4514301  
12.0014401  
12.1514501  
12.3014601  
12.4514701  
13.0014801  
13.1514901  
13.3015001  
13.4515101  
14.0015201  
14.1515301  
14.3015401  
14.4515501  
15.0015601  
15.1515701  
15.3015801  
15.4515901  
16.0016001  
16.1516101  
16.3016201  
16.4516301  
17.0016401  
17.1516501  
17.3016601  
17.4516701  
18.0016801  
18.1516901  
18.3017001  
18.4517101  
19.0017201  
19.1517301  
19.3017401  
19.4517501  
20.0017601  
20.1517701  
20.3017801  
20.4517901  
21.0018001  
21.1518101  
21.3018201  
21.4518301  
22.0018401  
22.1518501  
22.3018601  
22.4518701  
23.0018801  
23.1518901

42019740  
20 192.  
0.15193.  
0.30194.  
0.45195.  
1.00195.  
1.15197.  
1.30198.  
1.45199.  
2.00200.....

**STATION 10 PLAN 10 RATIC 6**

卷之二

1110.0	1110.3	1110.6	1110.9	1111.4	1111.8	1112.4	1112.7
1113.7	1114.0	1114.3	1114.6	1114.9	1115.2	1115.5	1115.8
1117.3	1117.0	1116.7	1116.5	1116.0	1116.2	1116.3	1116.6
1124.9	1129.9	1130.5	1131.0	1131.3	1131.5	1131.7	1132.0
1132.4	1122.2	1122.5	1132.6	1132.5	1132.4	1132.3	1132.2
1131.0	1131.6	1131.5	1131.3	1131.2	1131.0	1130.5	1130.7
1130.4	1130.3	1130.1	1130.0	1129.8	1129.6	1125.4	1125.3
							1129.1

PEAK JUFTLOW IS 7367. AT TIME 43.50 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	7367.	5931.	1967.	968.	19361.
CHS	209.	168.	56.	27.	2482.
INCHES					
NH		12.1A	16.1B	16.57	16.57
ACFT		309.37	410.37	420.77	420.77
TULS CU M	ACFT	2941.	3901.	4000.	4000.
		3628.	4812.	4934.	4934.



15.00	681
15.15	611
15.30	621
15.45	631
15.60	641
15.75	651
15.90	661
16.45	671
17.00	681
17.15	691
17.30	701
17.45	710
18.00	720
18.15	730
18.30	740
18.45	750
19.00	760
19.15	770
19.30	780
19.45	790
20.00	800
20.15	810
20.30	820
20.45	830
21.00	840
21.15	850
21.30	860
21.45	870
22.00	880
22.15	890
22.30	900
22.45	910
22.60	920
23.15	930
23.30	940
23.45	951
0.	961
0.15	971
0.30	981
0.45	991
1.00	1001
1.15	101
1.30	102
1.45	1031
2.00	1041
2.15	1051
2.30	1061
2.45	1071
3.00	1081
3.15	1091
3.30	1101
3.45	1111
4.00	1121
4.15	1131
4.30	1141
4.45	1151
5.00	1161
5.15	1171
5.30	1181
5.45	1191
6.00	1201
6.15	1211
6.30	1221
6.45	1231



0. 172.  
0.15171.  
0.30154.  
0.45135.  
1.00126.  
1.15137.  
1.30138.  
1.45139.  
2.00230.

PEAK FLOWS AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS				
				RATIO 1 0.20	RATIO 2 0.40	RATIO 3 0.50	RATIO 4 0.60	RATIO 5 0.70
HYDROGRAPH AT	1 4.53 (19079.77)	1 { 41.93){	1441. 83.86){	2762. 104.63){	3702. 125.80){	4442. 167.73){	5923. 166.73){	7404. 209.66){
ROUTED TO	1 4.53 (19079.77)	1 { 28.35){	1001. 80.05){	2827. 104.16){	3678. 125.15){	4420. 166.88){	5493. 166.88){	7367. 208.60){

## SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....

	ELEVATION	INITIAL VALUE	SPILLWAY CREST	TCP OF DAM
STORAGE	1112.90	1112.90	1134.61	
OUTFLOW	242.	242.	899.	
	55.	55.	11546.	

RATIO	MAXIMUM R.F. SERVIR	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM GUTTER CFS	CLARIFICATION CYFR TCP	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
CF	1.05 FLEV	0.	649.	1001.	C.	45.57	C.
PF	1127.69	0.	729.	2827.	C.	44.00	C.
0.20	1130.22	0.	749.	3678.	C.	43.50	C.
0.40	1130.75	0.	763.	4420.	C.	43.50	C.
0.50	1131.11	0.	791.	5893.	C.	43.50	C.
0.60	1131.83	0.	819.	7367.	C.	43.50	C.
0.80	1132.95	0.					
1.00							

**APPENDIX D**

**REFERENCES**

APPENDIX D  
REFERENCES

- 1) U.S. Department of Commerce, Technical Paper No. 40, Rainfall Frequency Atlas of the United States, May 1961.
- 2) Soil Conservation Service, National Engineering Handbook, Section 4, Hydrology, August 1972 (U.S. Department of Agriculture).
- 3) H.W. King and E.F. Brater, Handbook of Hydraulics, 5th edition, McGraw-Hill, 1963.
- 4) T.W. Lambe and R.V. Whitman, Soil Mechanics, John Wiley and Sons, 1965.
- 5) W.D. Thornbury, Principles of Geomorphology, John Wiley and Sons, 1969.
- 6) University of the State of New York, Geology of New York, Education Leaflet 20, Reprinted 1973.
- 7) Cornell University Agriculture Experiment Station (compiled by M.G. Cline and R.L. Marshall), General Soil Map of New York State and Soils of New York Landscapes, Information Bulletin 119, 1977.

APPENDIX E

STABILITY ANALYSIS

UNITED STATES DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE - Soil Mechanics Laboratory

800 "J" Street, Lincoln, Nebraska 68508

SUBJECT: ENG 22-5, New York WP-03, Nanticoke Creek  
Site No. 10 (Broome County)

DATE: January 29, 1970

TO: Richard J. Phillips, State Conservation Engineer  
SCS, Syracuse, New York

ATTACHMENTS

1. Form SCS-354, Soil Mechanics Laboratory Data, 1 sheet.
2. Form SCS-355A, Triaxial Shear Test Data, 2 sheets.
3. Form SCS-352, Compaction and Penetration Resistance Report, 4 sheets.
4. Form SCS-130, Drain Materials, 1 sheet.
5. Form SCS-357, Summary - Slope Stability Analysis, 2 sheets.

DISCUSSION OF DATA

FOUNDATION MATERIALS

A. Classification. Bedrock at the site is shale and siltstone of the Upper Devonian Group. In both abutments glacial till overlies the bedrock, except in the steep right abutment where the bedrock outcrops and is covered by a thin, loose mantle of colluvium classifying as ML, which contains rock.

In the left abutment the till is 23 to 30 feet deep over bedrock in the area of the emergency spillway. Between here and the channel, investigation drilling did not reach bedrock. This till, based on samples, is coarse with 43 to 52 percent finer than the No. 200, and 70 to 65 percent passing the No. 4, classifying as CL-ML and GC. Above the emergency spillway the soil is finer grained, consisting of 8 to 11 feet of till overlying glacio-lacustrine deposits. These are field classified as ML and CL-ML.

In the right abutment, under the emergency spillway location, the bedrock slope flattens, making a bench or shelf where the till covering is up to 27 feet thick. Based on the submitted sample, this till is CL-ML with a liquid limit of 22 and a plasticity index of 4. Seventy-three percent of the sample is finer than the No. 200.

In the channel area is a stream deposit of sand and gravel with some silt up to about 12 feet deep, and lying on till or bedrock on centerline. To the left of the channel the floodplain is overlain with 2 to 3 feet of soft ML, which based on a submitted sample has a liquid limit of 33 and a plasticity index of 5.

Richard J. Phillips

2

Subj: ENG 22-5, New York WP-03, Nanticoke Creek, Site 10

B. Blow Count. Blow counting was done in the till on centerline in Holes 252, 51, 52, 53, and 261. The minimum counts in these holes varied from 22 to 27 per foot and the maximum counts from 68 to 175 per foot.

Blow counting in the alluvial GM-GP and the underlying till in Holes 351, 352, and 353 on the principal spillway line indicate blows from 29 to 76 per foot in the alluvium, and from 20 to 90 per foot in the till (one count of 170 per foot was probably due to a rock).

C. Consolidation. Except for the 2 to 3 feet of soft ML in the floodplain there should be very little consolidation in the foundation.

D. Permeability. Field permeability testing (Hole 352) indicates that the irregularly stratified alluvial gravels in the channel area have a permeability rate of 85.5 fpm but that the till underlying the gravels is practically impermeable. In a continuation of this same hole into the bedrock, a total pressure of 40 psi produced a water loss of 0.9 gpm over a 17-foot depth of hole.

In Hole 353, pumping at 30 psi between depths 22 and 27 feet showed a rate of 0.94 gpm, but between depths 18 and 27 feet it showed a rate up to almost 11 gpm. It is conjectured that fractured zones in the surface 5 feet of bedrock were being opened up, or washed free of clay seams.

Pump testing at 42.6 psi in Hole 53 in the right abutment shows a similar situation. In testing the entire 28 feet of bedrock hole (11 to 39 feet) a loss of 19.2 gpm occurred. In testing only the bottom 15 feet (24 to 39 feet), a loss of 8 gpm was recorded. This would indicate fracturing and weathering in the upper portion.

Water was found in the floodplain at creek level. In Holes 4 and 252 water was found at bedrock contact.

E. Shear Strength. Removal of some of the floodplain surface ML is contemplated. The alluvial gravels and glacial tills have more than enough strength to carry the proposed structure. Shear testing was not done.

#### EMBANKMENT MATERIALS

A. Classification and Compacted Dry Density. Four samples were submitted to represent the borrow. Following is a table showing the gradation and standard Proctor density of these soils:

Sample No. Laboratory	Field	LL	PI	Classifi- cations	Gradation		Proctor Density pcf	Optimum Moisture %
					Minus 200	Minus No. 4		
70W730	301.1	33	5	ML	77	100	98.0	22.0
70W731	202.1	24	7	CL-ML	52	70	123.5	12.0
70W732	209.2	24	9	GC	48	65	124.5	11.5
70W733	224.1	22	4	CL-ML	73	85	118.0	14.0

Richard J. Phillips

3

Subj: ENG 22-5, New York WP-03, Nanticoke Creek, Site 10

Of these samples 70W730 is moderately dispersed, the other three only slightly so.

Sample 70W730 represents the soft surface ML in the floodplain which may be removed from under the proposed dam. The other three samples are from the emergency spillways.

- B. Permeability. Even though the borrow contains sand and gravel, it appears well graded and seepage through the dam is expected to be minimal.
- C. Shear Strength. Samples 70W730 and 70W733 were tested in triaxial consolidated undrained shear on the minus No. 4 material at 95 percent of standard Proctor density. At about 91 percent of theoretical full saturation, shear parameters for the ML, 70W730, are  $\phi = 24^\circ$ ,  $c = 850$  psf. For the CL-ML, 70W733, at about 97 percent of full saturation, parameters are  $\phi = 25^\circ$ ,  $c = 825$  psf.
- D. Consolidation. It is estimated that the maximum section of the embankment (channel section) will consolidate an average of 0.03 ft/ft. The portion of the embankment basing at permanent pool elevation will consolidate an average of 0.02 ft/ft.

#### STABILITY ANALYSIS

The maximum section was checked for slope stability using each embankment shear value and a foundation value of  $\phi = 35^\circ$ ,  $c = 0$  psf. A minimum factor of safety of 1.63 was found for the upstream slope with an arc cutting about 23 feet into the foundation. The analysis is shown on Form SCS-357.

#### SETTLEMENT ANALYSIS

It has been stated that the right abutment where the bedrock outcrops, or nearly so, is quite steep and could be a source of differential settlements.

#### CONCLUSIONS AND RECOMMENDATIONS

- A. Special Site Factors. We concur with the engineer's suggestion that the bedrock slopes, particularly in the right abutment, be flattened to 2:1 if the rock is not too hard. A reluctant alternative would be a wider than normal core trench cut back to a 2:1 slope in the abutment.

It is suggested that the soft surface ML be removed from under the downstream half of the embankment and be placed in the channel area upstream from the dam to make a continuous blanket over the alluvial gravels, as far upstream as is feasible.

- B. Cutoff. The till soils are evidently deeper over the bedrock in the left abutment than in the right abutment. In the left abutment the cutoff trench should cut off the topsoil and bottom in firm till.

Richard J. Phillips  
Subj: ENG 22-5, New York WP-08, Nanticoke Creek, Site 10

4

In the right abutment, because of the permeable nature of the surface bedrock, the trench should, if possible, bottom in firm bedrock.

Across the floodplain, complete cutoff of the alluvial gravels would be most desirable. It is suggested that an attempt be made to provide cutoff to the till. If this should fail, then cutoff to whatever depth is attainable should be accomplished.

Backfill with the till borrow. Suggested placement density is 95 percent of standard Proctor, at near optimum moisture with the control based on the minus No. 4 fraction.

- C. Principal Spillway. Both settlement under and elongation in the pipe will be minimum values.

Backfill with till borrow to a suggested 95 percent of standard Proctor density, at near optimum moisture.

Use a  $\phi$ -angle of  $30^\circ$  for conduit loading computations.

- D. Drainage. Drainage is recommended below approximate emergency spillway elevation. A trench drain is suggested at the c/b = 0.7 point.

In the left abutment this should bottom in the till, about the same depth as the cutoff trench. In the upper right abutment the drain should contact the bedrock, which is pervious. On the steep rock right abutment a blanket drain may better serve the purpose. Suggested location is between the c/b points 0.6 and 0.8.

Across the floodplain, depth of the trench will depend on the degree of cutoff attained. If it is felt that the cutoff is good, then suggested trench depth is half the depths of the gravels. However, if only partial cutoff has been obtained, then the drain trench should penetrate to near full depth of the gravels.

A coarse gradation similar to ASTM No. 78 Road Gravel, shown on Form SCS-130, is suggested as drain material. It is suggested that the coarsest gradation of till available be laid as a base for the downstream section of the dam where the ML has been removed in order to provide a transition zone between the fill and the coarse-grained alluvium.

- E. Embankment Design. If the floodplain ML under the downstream portion of the dam is not all used in upstream blanketing; the remainder may be placed in the center portion of the dam. The till borrow may be placed without selection.

Suggested placement density is 95 percent of standard Proctor at near optimum moisture, with control on the minus No. 4 material.

Richard J. Phillips

5

Subj: ENG 22-5, New York WP-08, Nanticoke Creek, Site 10

The suggested 3:1 upstream slope with a 10-foot berm, and 2 1/2:1 downstream slope with drainage provide good factors of safety.

Overbuild the dam by about one foot to compensate for settlement in the embankment.

Prepared by:

Carl G. Nygren  
Carl G. Nygren

Reviewed and Approved by:

Lorn P. Dunnigan  
Lorn P. Dunnigan

Attachments

cc:

Richard J. Phillips (1)  
Bernard S. Ellis, Syracuse, New York  
D. W. Shanklin, Binghamton, New York  
Neil F. Bogner, Upper Darby, Pa.

revision

10/21/60

Ht. = 58'  
79,000 cy

**Class "C"**  
**Floodwater Retarding**

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

"C"

## water Retarding

U S DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

SOIL MECH  
LABORATORY  
1



MATERIALS  
TESTING REPORTU. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

## TRIAXIAL SHEAR TEST

PROJECT AND STATE

FIELD SAMPLE NO.

DEPTH

GEOLOGIC ORIGIN

SAMPLE LOCATION

TYPE OF SAMPLE

TESTED AT

APPROVED BY

DATE

## INDEX TEST DATA

USCS 1. 11 ALL 2.2; PI 1  
 % FINER (mm): 0.002 15; 0.005 2.5;  
 0.074 (# 200) 7.5  
 $G_s (-\#4)$  1.6";  $G_s (+\#4)$  2.71"  
 STANDARD:  $\gamma_d$  MAX. 11.0 pcf;  $w_o$  11.0%  
 MODIFIED:  $\gamma_d$  MAX. pcf;  $w_o$  %

## SPECIMEN DATA

HEIGHT 5.0"; DIAMETER 1.4"  
 MATERIALS TESTED PASSED 5/4" SIEVE  
 METHOD OF PREPARATION STATIC 3  
 LAYER COMPACTION & SOAKED  
 MOLDING MOISTURE 16.4%  
 MOLDED AT 24.4% OF  $\gamma_d$  MAXIMUM

## TYPE OF TEST

- UU   
 CU   
 CQ   
 CD

## DRY DENSITY

INITIAL  
pcf   
g/cc CONSOLIDATED  
pcf   
g/cc 

## MOISTURE CONTENT, %

START  
OF  
TESTDEG. OF SAT.  
AT START  
OF TESTEND  
OF  
TEST

(hrs)

TIME OF  
CONSOLI-  
DATION  
(hrs)MINOR  
PRINCIPAL  
STRESS  
 $\sigma_3$  (psi)DEVIATOR  
STRESS  
 $\sigma_1 - \sigma_3$   
(psi)AXIAL  
STRAIN AT  
FAILURE,  
 $\epsilon$  (%)

112.0

112.1

112.2

17.7

18.1

17.9

94.6

17.4

16.5

10


5.93

5.77

32.8

30

30

DEVIATOR STRESS ( $\sigma_1 - \sigma_3$ ), psiREMARKS AVERAGE TEST  $\gamma_d = 95.0\%$  STD.


MAY 1944 7041730

STATE NAME	U. S. DEPARTMENT OF AGRICULTURE		COMPACTION AND PENETRATION RESISTANCE	
TESTING UNIT NUMBER		SOIL CONSERVATION SERVICE		

LOCATION: Long Island, Site 10, New York.

FIELD SAMPLE NO. <u>Soil 1</u> <u>Soil 2</u>	LOCATION <u>Prim. Spwy D</u> <u>D</u>	TESTED AT <u>SML-LINCOLN</u>	APPROVED BY	DEPTH <u>0-1.1'</u> <u>0-2'</u>
--	---	---------------------------------	-------------	---------------------------------------

CLASSIFICATION <u>ML</u>	LL <u>33</u>	PI <u>5</u>	CURVE NO. <u>1</u> OF <u>1</u>
MAX. PARTICLE SIZE INCLUDED IN TEST	<u>&lt; 1/4"</u>		
SPECIFIC GRAVITY ( $G_s$ )	{ MINUS NO. 4 <u>2.70</u> PLUS NO. 4 <u>-</u>		
	STD (ASTM D-698) <input checked="" type="checkbox"/> ; METHOD <u>A</u>		
	MOD (ASTM D-1557) <input type="checkbox"/> ; METHOD <u>-</u>		
	OTHER TEST <input type="checkbox"/> (SEE REMARKS)		




REMARKS

U.S. DEPARTMENT OF AGRICULTURE  
TESTING REPORT U.S. DAIRY INFORMATION SERVICE

COMPACTION AND  
PENETRATION RESISTANCE

FIELD SAMPLE NO. <u>2021</u>	LOCATION <u>L. E. M. R. Spwy. (B) Corbett Till.</u>	DEPTH <u>6-16'</u>
GEOLOGIC ORIGIN <u>SML-LINCOLN</u>	TESTED AT <u>SML-LINCOLN</u>	APPROVED BY <u></u>
CLASSIFICATION <u>CL-ML LL 24 PI 7</u>	CURVE NO. <u>2</u> OF <u>4</u>	
MAX. PARTICLE SIZE INCLUDED IN TEST <u>&lt; #7 "</u>	STD (ASTM D-698) <input checked="" type="checkbox"/> ; METHOD <u>A</u>	
SPECIFIC GRAVITY ( $G_s$ ) { MINUS NO. 4 <u>2.80</u> PLUS NO. 4 <u>2.73</u>	MOD (ASTM D-1557) <input type="checkbox"/> ; METHOD <u></u>	
OTHER TEST <input type="checkbox"/> (SEE REMARKS)		




REMARKS	CURVE IS FOR THE MINUS NO. 4 FRACTION GRADATION OF TOTAL SAMPLE	
< NO. 200 <u>52</u> ; < NO. 4 <u>70</u> ; < 6 in. <u>100</u>		

700071

U.S. DEPARTMENT OF AGRICULTURE THE SOIL CONSERVATION SERVICE	COMPACTION AND PENETRATION RESISTANCE	
---	--	--

FIELD NUMBER 204-2	LOCATION L. E. M. Spring, (C) Medium Till	DEPTH 13-18'
GEOL. ORIGIN SML-LINCOLN	TESTED AT SML-LINCOLN	APPROVED BY DATE
CLASSIFICATION G-C	LL 24 PI 9	CURVE NO. 3 OF 4
MAX. PARTICLE SIZE INCLUDED IN TEST - 7.4 "		STD (ASTM D-698) <input checked="" type="checkbox"/> ; METHOD A
SPECIFIC GRAVITY ( $G_s$ ) { MINUS NO. 4 2.84		MOD (ASTM D-1557) <input type="checkbox"/> ; METHOD _____
PLUS NO. 4 2.73		OTHER TEST <input type="checkbox"/> (SEE REMARKS)



REMARKS  
CURVE IS FOR THE MINUS NO. 4 FRACTION  
GRADATION OF TOTAL SAMPLE  
< NO. 200 42%; < NO. 4 65%; < 6 IN. 10.2%

MATERIALS TESTING REPORT		U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE		COMPACTION AND PENETRATION RESISTANCE	
<i>Westgate Creek, Site 10, New York.</i>					
FIELD SAMPLE NO. <u>224-1</u>	LOCATION <u>R. EML SPWY. (C) Finest T.H.</u>			DEPTH <u>0.5 - 13.5'</u>	
GEOLOGIC ORIGIN		TESTED AT <u>SML-LINCOLN</u>	APPROVED BY	DATE	
CLASSIFICATION	CL-ML LL 22 PI 4	CURVE NO. 4 OF 4			
MAX. PARTICLE SIZE INCLUDED IN TEST	<u>&lt; 3/8"</u>	STD (ASTM D-698) <input checked="" type="checkbox"/> ; METHOD <u>A</u>			
SPECIFIC GRAVITY ( $G_s$ )	MINUS NO. 4 <u>2.69</u> PLUS NO. 4 <u>2.71</u>	MOD. (ASTM D-1557) <input type="checkbox"/> ; METHOD _____			
OTHER TEST <input type="checkbox"/> (SEE REMARKS)					
<p>Graph showing Penetration Resistance (psi) versus Depth (inches). The resistance decreases from approximately 2200 psi at 0.5 inches to about 300 psi at 13.5 inches.</p>					
<p>Graph showing Density of Compacted Soil (pcf) versus Moisture Content (% of dry weight). The density curve peaks at 14% moisture content (optimal) and is labeled "OPT. MOIST.".</p>					
<p>Graph showing Compaction Curves (dry density vs moisture content). The curves include "DRY DENSITY", "OPT. DENSITY", "30% COMPLETE SATURATION", and "ZERO AIR VOLUME".</p>					
REMARKS	CURVE IS FOR THE MINUS NO. 4 FRACTION GRADATION OF TOTAL SAMPLE <u>&lt; No. 200 75%</u> ; <u>&lt; No. 4 85%</u> ; <u>&lt; 2 in. 100%</u>				

MATERIALS  
TESTING REPORT

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE


## DRAIN MATERIALS

《新編中華書局影印》

卷之三

1

1041




MATERIALS U.S. DEPARTMENT OF AGRICULTURE  
DIVISION OF SOIL CONSERVATION SERVICE

SUMMARY - SLOPE STABILITY ANALYSIS


PROJECT OR STATE		NAME & ADDRESS		DATE	
				12-1-59	
METHOD OF ANALYSIS		CUTTED AREA		NEW FORM	
SOURCE AND USE OF MATERIALS	CLASSIFICATION	ADSORBENT	DATA	REMARKS	
No.	Y <sub>d</sub> (psi)	Y <sub>m</sub> (psi)	Y <sub>s</sub> (psi)	Ton/c (psi)	c (psi)
1. DRAIN	0.7	1.05	1.32	35.0	700
2. EMBANKMENT	0.7	1.05	1.25	34.0	0
3. CUTTED AREA	0.7	1.05	1.25	34.0	35.0
4.				25.0	32.5
5.					
6.					
7.					
8.					
9.					
10.					
11.					
12.					
13.					
14.					
15.					
16.					
17.					
18.					
19.					
20.					
21.					
22.					
23.					
24.					
25.					
26.					
27.					
28.					
29.					
30.					
31.					
32.					
33.					
34.					
35.					
36.					
37.					
38.					
39.					
40.					
41.					
42.					
43.					
44.					
45.					
46.					
47.					
48.					
49.					
50.					
51.					
52.					
53.					
54.					
55.					
56.					
57.					
58.					
59.					
60.					
61.					
62.					
63.					
64.					
65.					
66.					
67.					
68.					
69.					
70.					
71.					
72.					
73.					
74.					
75.					
76.					
77.					
78.					
79.					
80.					
81.					
82.					
83.					
84.					
85.					
86.					
87.					
88.					
89.					
90.					
91.					
92.					
93.					
94.					
95.					
96.					
97.					
98.					
99.					
100.					
101.					
102.					
103.					
104.					
105.					
106.					
107.					
108.					
109.					
110.					
111.					
112.					
113.					
114.					
115.					
116.					
117.					
118.					
119.					
120.					
121.					
122.					
123.					
124.					
125.					
126.					
127.					
128.					
129.					
130.					
131.					
132.					
133.					
134.					
135.					
136.					
137.					
138.					
139.					
140.					
141.					
142.					
143.					
144.					
145.					
146.					
147.					
148.					
149.					
150.					
151.					
152.					
153.					
154.					
155.					
156.					
157.					
158.					
159.					
160.					
161.					
162.					
163.					
164.					
165.					
166.					
167.					
168.					
169.					
170.					
171.					
172.					
173.					
174.					
175.					
176.					
177.					
178.					
179.					
180.					
181.					
182.					
183.					
184.					
185.					
186.					
187.					
188.					
189.					
190.					
191.					
192.					
193.					
194.					
195.					
196.					
197.					
198.					
199.					
200.					
201.					
202.					
203.					
204.					
205.					
206.					
207.					
208.					
209.					
210.					
211.					
212.					
213.					
214.					
215.					
216.					
217.					
218.					
219.					
220.					
221.					
222.					
223.					
224.					
225.					
226.					
227.					
228.					
229.					
230.					
231.					
232.					
233.					
234.					
235.					
236.					
237.					
238.					
239.					
240.					
241.					
242.					
243.					
244.					
245.					
246.					
247.					
248.					
249.					
250.					
251.					
252.					
253.					
254.					
255.					
256.					
257.					
258.					
259.					
260.					
261.					
262.					
263.					
264.					
265.					
266.					
267.					
268.					
269.					
270.					
271.					
272.					
273.					
274.					
275.					
276.					
277.					
278.					
279.					
280.					
281.					
282.					
283.					
284.					
285.					
286.					
287.					
288.					
289.					
290.					
291.					
292.					
293.					
294.					
295.					
296.					
297.					
298.					
299.					
300.					
301.					
302.					
303.					
304.					
305.					
306.					
307.					
308.					
309.					
310.					
311.					
312.					
313.					
314.					
315.					
316.					
317.					
318.					
319.					
320.					
321.					
322.					
323.					
324.					
325.					
326.					
327.					
328.					
329.					

NANTICOKE SITE #10  
NEW YORK

MAXIMUM SECTION  
STATION 8+37




NANTICOKE 15 SITES \$10  
NEW YORK  
MAXIMUM SECTION  
STATION 8+37




APPENDIX F

DRAWINGS



## VICINITY MAP



TOPOGRAPHIC MAP

# NANTICOKE CREEK WATERSHED PROJECT

## FLOODWATER RETARDING DAM SITE 10

DRAINAGE AREA	2902 Acres
FLOOD STORAGE TO EMERGENCY SPILLWAY CREST	618 Ac.Ft.
WATER SURFACE AREA AT SEDIMENT POOL	4.8 Acres
HEIGHT OF DAM	58 Feet
VOLUME OF FILL	108,380 <del>101,400</del> Cu.Yds.

BUILT UNDER THE WATERSHED PROTECTION AND  
FLOOD PREVENTION ACT

BY  
COUNTY OF BROOME  
WITH THE ASSISTANCE OF THE  
SOIL CONSERVATION SERVICE  
OF THE

U. S. DEPARTMENT OF AGRICULTURE

### INDEX

SHEET 1- COVER SHEET	
SHEET 2- ACCESS ROAD DETAILS	
SHEET 3- PLAN OF STORAGE AREA	
SHEET 4- PLAN OF STRUCTURAL WORKS	SHEET 4A LOCATION OF DIVERSIONS, TILE LINES, + ROCK-LINED DITCHES
SHEET 5- LAYOUT DATA	
SHEET 6- CUTOFF TRENCH EXCAVATION	
SHEET 7- EAST EMERGENCY SPILLWAY	
SHEET 8- WEST EMERGENCY SPILLWAY	
SHEET 9- FILL PLACEMENT & PRINCIPAL SPILLWAY EXCAVATION	
SHEET 10- DRAINAGE SYSTEM	
SHEET 11- DRAINAGE SYSTEM	
SHEET 12- PLAN PROFILE OF PRINCIPAL SPILLWAY	
SHEET 13- RISER STRUCTURAL DETAILS	SHEET 13A RISER STRUCTURAL DETAILS
SHEET 14- RISER STRUCTURAL DETAILS	
SHEET 15- RISER STRUCTURAL DETAILS	
SHEET 16- RISER STRUCTURAL DETAILS	
SHEET 17- RISER TRASH RACKS	
SHEET 18- CONDUIT DETAILS	
SHEET 19- CRADLE AND BENT DETAILS	
SHEET 20- RESERVOIR DRAIN INLET DETAILS	
SHEET 21- FENCING DETAILS	
SHEET 22- LOGS OF TEST HOLES	
SHEET 23- LOGS OF TEST HOLES	
DRAWING NO. NY -2010-P-A	ADDENDUM TO RISER STRUCTURAL DETAILS

CONTRACTOR  
GOVT. REP. —  
INSPECTOR —

CONTRACT NO. +  
TOTAL COST

# WATERSHED PROJECT

## DAM SITE 10

AS BUILT  
9-13-79



2902 Acres

618 Ac.Ft.

4.8 Acres

58 Feet

108,380 TOT. 400 Cu.Yds.



LOCATION MAP

CONTRACTOR - BESTWAY CONSTR. CO., INC.

GOV'T. REP. - D. LAKE (10/6/77 - 6/25/78) + G. PAGE (6/26/78 - 9/13/78)

INSPECTOR - J. MOTT (10/18/77 - 1/8/78), J. BARLOW (1/9/78 - 5/30/78)

R. GEMMEL (5/31/78 - 9/18/79)

CONTRACT NO. + DATE - NAN-10-TI 10/31/77

TOTAL COST - \$ 453,752.92

0 1 2 3 Miles

SCALE

85D-3946


NY-713

STRUCTURAL DETAILS

EXCAVATION

STRUCTURAL DETAILS

NANTICOKE CREEK WATERSHED PROJECT	
FLOODWATER RETARDING DAM	
BROOME COUNTY, NEW YORK	
COVER SHEET	
U.S. DEPARTMENT OF AGRICULTURE	
SOIL CONSERVATION SERVICE	
DEW	SOIL CONSERVATION SERVICE
1-77	NY-2010-0



**AS BUILT**

9-13-79

SLOPE 4% LENGTH 250  
APPROX VOL 100 CY EXCAVATION 125 CY TYPICAL FOR REACH 1  
RIPRAP 125 CY

10' C.L.  
ORIGINAL GROUND LINE  
SECTION OF DIVERSION  
TYPICAL FOR REACH 1  
APPROX SLOPE 14% LENGTH 350  
APPROX VOL 150 CY EXCAVATION 460 CY  
RIPRAP 340 CY

ABUTMENT EXCAVATION  
SLOPE THE RIGHT AND LEFT TO 24 SLOPES SEE SHEET 1 FOR SLOPE EXCAVATION LIMITS  
HO-UPSTREAM TO 160 FEET STREAM FROM E OF C.M.  
ALL EXPOSED ROCK SHALL BE CLEARED OF LOOSE MATERIAL PRIOR TO PLACEMENT OF EARTH FILL.  
SEE MODIFICATION NO 4 FOR DETAILS

FOUNDATION EXCAVATION  
EXCAVATE THE SANDY SOIL WITH ORGANIC MATERIAL (AS REPRESENTED BY TP 303 FROM 0 TO 2.0') FRONT THE BASE WIDTH OF DAM IN THE FLOOD PLAIN. SEE SHEET 6

SOILS DETAILS  
SEE SHEETS 22 & 23 FOR DESCRIPTIONS OF TEST PITS AND DRILL HOLES SHOWN ON SHEETS 4, 6, 7, 8, 9, 10 & 12

BENCH MARK DESCRIPTION  
BM ELEV 1080.52  
S.C.S. STANDARD D.S.P. 10-00  
BENT NAIL IN ROOT OF 40 MAPLE TREE WITH TREEHOUSE

**NANTICOKE CREEK WATERSHED PROJECT**

**SITE 10**

**FLOODWATER RETARDING DAM  
BROOME COUNTY, NEW YORK**

**PLAN OF STRUCTURAL WORKS**

**U.S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE**


D.L. CHAPMAN 1000

D. ANGELO 1000

C. BURTON 1000

J. WILSON 1000

NY-2010-P



**AS BUILT**

STRIPPED GROUND OR  
FOUNDATION EXCAVATION LINE

TRANSITION FROM  
12' TO 22'

SECTION OF CUTOFF TRENCH @ STA. 7.00  
TYPICAL FROM STA. 6.50 TO STA. 7.50 AND FROM  
STA. 8.50 TO 9.50

SECTION OF CUTOFF TRENCH @ STA. 8.00  
TYPICAL FROM STA. 7.50 TO STA. 8.50

STA 7.00  
ELEV 135.6

STA 8.00  
ELEV 135.6

E

WEST  
EMERGENCY  
SPILLWAY

DH-266-S DOWNSTREAM E

DH-264

CL-ML  
Sh- Sl St

1140

1120

1100

1080

1100  
2-00


INTERFACE BETWEEN ABUTMENT AND  
EMBANKMENT SHALL BE NO STEEPER  
THAN TWO (2) HORIZONTAL TO ONE (1)  
VERTICAL

PRINCIPAL SPILLWAY  
@ STA. 7.74

E


TP4-0 UPSTREAM E

ELEV 134.6



SECTION OF EMERGENCY SPILLWAY AT STATION 3+00


TYPICAL FROM STA. 2+50 TO APPROX. STA. 6+55. EXCAVATION LIMITS TO DESIGN BOTTOM APPROX. STA. 1+60 TO STA. 2+50.



AS BUILT



9-13-79

SPILLWAY



2.5  
DESIGN BOTTOM

SECTION




NANTICOKE CREEK WATERSHED PROJECT  
SITE 10

FLOODWATER RETAINING DAM  
BROOME COUNTY, NEW YORK  
EAST EMERGENCY SPILLWAY


U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

HARPER 100  
RUSSELL 050




SECTION OF EMERGENCY SPILLWAY AT STA. 3+50



TYPICAL FROM STA. 2+50 TO APPROX. STA. 7+15.  
EXCAVATION LIMITS TO DESIGN BOTTOM IN SECTION  
WHERE BED ROCK IS ENCOUNTERED AT DESIGN  
GRADE AND FROM APPROX. STA. 1+50 TO STA.  
2+50



**AS BUILT**



SECTION OF LEVEE AT EMERGENCY SPILLWAY STA. 4+00  
TYPICAL FROM E. OF LEVEL SECTION @ STA 3+00 TO STA. 5+00 EMERGENCY SPILLWAY



NANTICOKE CREEK WATERSHED PROJECT  
SITE 10  
FLOODWATER RETARDING DAM  
BROOME COUNTY NEW YORK  
WEST EMERGENCY SPILLWAY  
U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE  
D. C. CHAPMAN 10/59  
C. BURDICK 10/59  
W. P. F. B. W.

AD-A092 036

NEW YORK STATE DEPT OF ENVIRONMENTAL CONSERVATION ALBANY F/6 13/13  
NATIONAL DAM SAFETY PROGRAM: NANTICOKE CREEK WATERSHED PROJECT --ETC(U)  
SEP 80 G KOCH

DACW51-79-C-0001


NL

UNCLASSIFIED


21x2  
47  
A294-D46




END  
DATE  
FILED  
1 81  
DTIC




SECTION OF DAM AT STATION 8+25 (NOT TO SCALE)  
TYPICAL FROM APPROX. STA 4+75 TO APPROX. STA. 9+90








SECTION 8+25 (NOT TO SCALE)

~~TO APPROX STA. 9+90~~



NANTICOKE CREEK WATERSHED P	
SITE 10	
FLOODWATER RETARDING DAM	
BROOME COUNTY, NEW YORK	
FILL PLACEMENT B PRIN. SPWY. EXC.	
U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE	
WA. RIEGEL	Date
LE. POLULECH	Approved by:
Drawn	1/21/
R.P. LEWIS	1/21/
Checked	1/21/
Comments	Sheet #1 Drawing No. 10-100
Charter	NY-20N



**AS BUILT**

9-13-77

QUANTITY SUMMARY

- 650 { 200 CU. YDS DRAIN FILL I (FINE)  
 460 CU. YDS. DRAIN FILL II (COARSE)  
 247 262 LIN FT. STRAIGHT SECTION OF 10" DIA  
 PERFORATED ASBESTOS - CEMENT PIPE  
 261 LIN FT. STRAIGHT SECTION OF 10" DIA  
 NON-PERFORATED ASBESTOS - CEMENT PIPE  
 2 END CAPS.  
 1 45° BEND - 10" DIA. CAST IRON  
 2 90° BENDS 10" DIA. CAST IRON

GRAIN SIZE DESCRIPTION FOR DRAIN FILL

1. DRAIN FILL I (FINE) SHALL MEET THE GRADE ASTM C33-67 FOR FINE AGGREGATE. IN ADDITION THE PERCENTAGE OF MATERIAL IN DRAIN FILL FINER THAN A #200 SIEVE SHALL NOT BE MORE THAN THREE (3) PERCENT
2. DRAIN FILL II (COARSE) SHALL MEET THE GRADE OF SIZE DESIGNATION I AS SHOWN IN TABLE 7 OF THE JANUARY 2, 1973 STANDARD SPECIFICATION OF THE NEW YORK STATE DEPARTMENT OF TRANSPORTATION. IN ADDITION, THE PERCENTAGE OF MATERIAL IN DRAIN FILL II FINER THAN A #200 SIEVE SHALL NOT BE MORE THAN THREE (3) PERCENT

DRAINAGE SYSTEM DETAILS

- (1) ASBESTOS CEMENT DRAIN PIPE SHALL CONFORM TO SPECIFICATION 545 AND SHALL BE 10" DIA. PRESSURE PIPE CLASS 200.


- (2) THE PROFILES AT THE BOTTOM OF ALL EXCAVATIONS AS SHOWN ARE ONLY APPROXIMATE. THE REQUIRED FINISHED GRADES WILL BE ESTABLISHED IN THE FIELD BY THE ENGINEER AT THE TIME OF CONSTRUCTION.

SECTIONS NOT TO SCALE

RIGHT ABUTMENT ALTERED DUE TO ROCK FOUNDATION VARIATIONS

- 8 OUTLET PIPE 10" DIA.  
 6 PRINCIPAL SPILLWAY  
 6 OUTLET PIPE 10" DIA.

ABUTMENT EXCAVATION  
 DETAILS SHEETS 6 & 9




NANTICOKE CREEK WATERSHED SITE 10  
 FLOODWATER RETARDING DAM  
 BROOM COUNTY, NEW YORK

U.S. DEPARTMENT OF AGRICULTURE  
 SOIL CONSERVATION SERVICE


Designed by	Approved by
W. A. BEGEL	12/79
Drawn by	File No.
H. MAYRIS	2/79
Typed by	Date
Clerk's Check	NY - 200

PROFILE ALONG C OF DRAIN (LOOKING DOWNSREAM)

✓





PLAN OF DRAIN OUTLETS



PROFILE ALONG DRAIN OUTLETS

0 5 10  
SCALE (FT)


**AS BUILT**  
9-13-71




**SMALL ANIMAL GUARD DETAILS**

(2 REQUIRED)



**DRAIN OUTLETS**



**OUTLETS**



<b>NANTICOKE CREEK WATERSHED PROJ.</b>	
<b>SITE 10</b>	
FLOODWATER RETARDING DAM	
BROOME COUNTY, NEW YORK	
<b>Drainage System</b>	
<b>U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE</b>	
Designed by WA. REED	Date 10/70
Drawn by R.P. LEWIS	Approved by _____ Title _____
Traced by _____	Per _____ Title _____
Edited by _____	Supervised by _____ Title _____
checked by _____	NY-2010-1
checked by _____	NY-2010-1
checked by _____	NY-2010-1



PLAN VIEW  
SCALE IN FEET

LOOS (EQU)


#### RIPRAP DETAILS

LOOSE ROCK SHALL BE PROPORTIONAL WEIGHT AS FOLLOWS:  
MAXIMUM WEIGHT 2000 LBS.  
75% OR MORE GREATER THAN 700  
MAXIMUM OF 5% LESS THAN 100  
75% OF THE SURFACE AREA SHALL  
COVERED WITH ROCK WHICH HAS A  
MINIMUM THICKNESS EQUAL TO 24


#### SECTION B-B (NOT TO SCALE)

#### RESERVOIR DRAIN PIPE DETAILS

USE STANDARD MECHANICAL JOINTS. PIPE SHALL CONFORM TO SPEC. 300 AND SHALL BE 16" NOMINAL DIA. CLASS 50, THICKNESS DESIGNATION 22. (30.0' TYPE III AND A 6.0' SECTION WITH A CAST OR SCREWED ASA 125 FLANGE.) TOTAL PIPE LENGTH = 36.0'



PROFILE ALONG S OF PRINCIPAL SPILLWAY



PLAN VIEW

**RIPRAP DETAILS**


LOOSE ROCK SHALL BE PROPORTIONED BY  
WEIGHT AS FOLLOWS:

MAXIMUM WEIGHT 2000 LBS.

75% OR MORE GREATER THAN 700 LBS.

MAXIMUM OF 5% LESS THAN 100 LBS.



75% OF THE SURFACE AREA SHALL BE  
COVERED WITH ROCK WHICH HAS A  
MINIMUM THICKNESS EQUAL TO 24"



**SECTION A-A (NOT TO SCALE)**

COLLAR	DIST FROM OUTLET	INVERT OF 42" DIA PIPE
I	76	1076.05
II	100	1077.05
III	124	1077.26
IV	148	1077.46
V	172	1077.67
VI	196	1077.87
VII	220	1077.17
VIII	244	1077.81
IX	268	1077.85
X	292	1077.89

ABOVE DIMENSIONS FOR LENGTHS OF PIPE ARE BASED ON NOMINAL LENGTH AND DO NOT INCLUDE CREEP.



RISER FOOTING CONCRETE

## NON-REINFORCED CONCRETE 30 CY



**NANTICOKE CREEK WATERSHED PROJECT  
SITE 10**  
**FLOODWATER RETARDING DAM**  
**BROOME COUNTY, NEW YORK**  
**PLAN PROFILE PRINCIPAL SPILLWAY**  
**U. S. DEPARTMENT OF AGRICULTURE**  
**SOIL CONSERVATION SERVICE**

DH #251, Left Emer. Spwy., Elev. 1145.5, D.B.C. 6/30-7/1/69

0.0
34 1.0 Material H (Topsoil)
31 Material BB (OC-GM)
41 16.0
32 17.0
36 17.0
40 Material Bg (OC-GM)
100/1 26.5

Notes: Auger refusal @ 26.5'. Brown gray boundary indistinct.

DH #252, Left Emer. Spwy., Elev. 1146.5, D.B.C. 6/18-19/69

0.0
10 1.5 Material H (Topsoil)
50 Material BB (OC-GM)
43 8.0 6/30/69
26 Material Bg (OC-GM)
46 17.5
51
50
33
93 Material Bg (OC-GM)
112 28.2
177 Material I (shalest)
100/R 36.0

Notes: Lots of water near rock surface. Badly weathered, 24.2-30.0'. Blind hole 31.3'-36.0'.

DH #253, Left Emer. Spwy., Elev. 1137.5, D.B.C. 6/30/69

0.0
11 1.5 Material H (Topsoil)
32 8.5 7/1/69 Material CB (CL-MG)
27 10.5
13.0 Material F (ML or SH)
26
44
45
35 Material E (CL-MG)
32
35
39 32.5

Material I (shalest)

Notes: Refusal @ 32.5'. Blind holes 2.0'-5.0', 7.0' 10.0', 12.0'-15.0'.

DH #254 Not Drilled

0.0
10 1.5 Material H (Topsoil)
32
44
45 Material BB (OC-GM)
46 23.0
112 26.0 Material Bg (OC)
48 Material E; (CL-MG)
53 29.0
100/R 32.0 Material F (ML or SH)
52 37.0

Notes: Auger refusal @ 37.0'. Blind hole 1.5'-5.0', 7.0'-10.0', 11.0-13.0', 13.0'-23.0', 29.0'-37.0'. Caved @ 9.0', no water. 6/20/69.

DH #255, Left Emer. Spwy., Elev. 1172.0, D.B.C. 6/2/69

0.0
38 1.5 Material H (Topsoil)
33 Material CB (CL-MG)
23 10.1
37 Material CG (CL)
27
49 18.1
74 Material E (CL-MG)
57 26.0
46 Material F (SH or ML)
37 32.5
40 Material CG (CL)
72 36.0

Notes: Hole caved @ 6.0', no water. Blind hole 1.5'-5.0', 6.5'-10.0', 11.5'-15.0'.

DH #257-260 - Not Drilled

DH #261, Right Emer. Spwy., Elev. 1138.4, D.B.C. 6/19-20/69

0.0
8 1.5 Material H (Topsoil)
40
45
38
27
27
35 Material CB (CL-MG)
57 100/1.5
42
60
56
52
63 6/19/69
77 24.2
100/1.2
28.6
100/1.5
AUG. 29.8

Notes: HS 18.0-20.0' to check. Run 1, 24.0-30.0', 100% holes, 1.5 5.0', 6.5'-10.0', 13.0', 14.5'-18.0'. Bed 13.0'-18.0'.

DH #263, Right Emer. Spwy., Elev. 1146.2

0.0
26 1.5 Material H (Topsoil)
38 6.0 6/30/69
23 Material CB (CL-MG)
115 18.0
25 Material CG (shalest)
100% 30.0

Notes: Run 1, 19.5-29.5, 100% 35.0, 100%. Auger refusal. Blind hole 1.5'-5.0', 6.5'-15.0', 13.0'-15.0', 15.0'-19.5'.

DH #264, Right Emer. Spwy., Elev. 1149.6

0.0
36 1.5 Material H (Topsoil)
32 6.0 6/30/69
35 Material CB (CL-MG)
115 18.0
25 Material CG (shalest)
100% 30.0

Notes: HS 18.0-20.0' to check. Run 1, 24.0-30.0', 100% holes, 1.5 5.0', 6.5'-10.0', 13.0', 14.5'-18.0'. Bed 13.0'-18.0'.

DH #351, Centerline Prin. Spwy., Elev. 1138.4

0.0
6 1.0 6/30/69
10 2.5
35
31
42
76
76
64
39
13.0
48
44
59
170 100/R
44
56
71
55
30.0

Notes: Blind hole 22.5-24.0'.

DH #352, Centerline Prin. Spwy., Elev. 1138.4

0.0
6 0.8 6/30/69
49 2.5
39
60 48.5 fpm
61 Material A (GM)
37 9.0
74
51 61
29
32
56
84 70
60 60/1.2
64
64
90
90
41
20
20
34.5
100% 34.5
PFT
Material CG (shalest)
100% 33.0
Notes: Refusal @ 34.5'. Run 2, 43.0-53.0', 100% PFT.

6/2/69

DH #265, Right Emer. Spwy., Elev. 1166.7, D.B.C. 6/23/69

	0.0
26	1.5 Material H (Topsoil)
38	6.0 Material Cb (CL-ML)
23	12.0 6/30/69 Material F (SM or ML)
38	7.5
38	Material Cb (CL-ML)
100/R	14.0
AUG	Material I (shale/silt)
NX	
100%	
NX	
100%	35.0

Note: Run 1, 19.5-29.5, 100%; run 2, 20.5-35.0, 100%. Auger refusal @ 19.5'. Blind hole 1.5'-5.0', 6.5'-10.0', 11.5'-13.0', 14.5'-18.0'. Boulders from 13.0'-18.0'.

DH #266, Right Emer. Spwy., Elev. 1169.8, D.B.C. 6/26/69

	0.0
30	1.5 Material H (Topsoil)
NH	32
NH	34 □ 6/30/69
NH	35 Material Cb (CL-ML)
NH	36
NH	115
NH	116
NH	117
NH	118 18.0
NH	119
NH	120 Material I (shale/silt)
NH	121
NH	122 30.0

Note: NB 18.0-20.0' to check for boulder. Run 1, 20.0-30.0', 100%. Blind holes, 1.5'-3.0', 6.5'-10', 11.5'-13.0', 14.5'-18.0'. Boulders from 13.0'-18.0'.

DH #351, Centerline Prin. Spwy., Elev. 1079.7, D.B.C. 6/26/69

	0.0
6	1.0 □ 6/30/69 Material D (ML)
10	2.5
35	
31	
42	
76	
64	
39	15.0
48	
64	
59	
170	
100/R	
NH	Boulder
64	
56	
71	
55	30.0

Note: Blind hole 22.5-24.0'.

DH #352, Centerline Prin. Spwy., Elev. 1079.8, D.B.C. 6/18.25/69

	0.0
6	0.8 □ 6/30/69 Material D (ML)
49	2.5
39	12.0 Material A (GM-GP)
64	1.0
61	1.0 fpm
37	
74	
51	
61	
29	
52	
54	
84	
76	
60	
38	Boulder
64	
30	
41	
30	
20	
100	35.0
100/R	
NX	
100%	PRT Material I (shale/silt)
NX	
100%	55.0

Note: Refusal @ 34.5', Run 1, 33.0'-43.0', 100%. Run 2, 45.0-55.0', 100%. Pressure tests tabulated in narrative.

DH #353, Centerline Pr. Spwy., Elev. 1077.1, D.B.C. 6/17/69

	0.0
3	2.0 □ 6/30/69 Material D (ML)
16	2.5
29	
40	
64	
66	
66	
62	12.0
61	
65	
50	16.7
50	
50	PRT 27.0 Material I (shale/silt)
50	
100%	

Note: Refusal @ 16.7'. Run 1, 17.0-27.0', 100%. Pressure tests tabulated in narrative.

LEGENDTEST HOLE NUMBERING SYSTEM

AS 0011

Centerline of dam	1-99
Borrow Area	101-199
Emergency spillway	201-299
Centerline of outlet structure	301-399
Stream channel	401-499
Relief Wells	501-599

UNIFIED SOIL CLASSIFICATION SYSTEM SYMBOLS

GW	Well graded gravels; gravel-sand mixtures
GP	Poorly graded gravels
GM	Silty gravels; gravel-sand-silt mixtures
GC	Clayey gravels; gravel-sand-clay mixtures
SW	Well graded sands; sand-gravel mixtures
SP	Poorly graded sands
SM	Silty sands; sand-silt mixtures
SC	Clayey sands; sand-clay mixtures
ML	Silts; silty, very fine sands; sandy or clayey, silty or gravelly clays
CH	Clays of high plasticity; fat clays
MH	Elastic silts; micaceous or diatomaceous silts
OL	Organic silts and organic silty clays of low plasticity
OM	Organic clays or silts of medium to high plasticity

NOTE: All classification shown in the logs are base on lab tests of samples representative of the material. Significant deviations from the normal are noted in the logs.

BEDROCK SYMBOLS

B	Basalt
Gn	Gneiss
Gr	Granite
Le	Limestone
Ma	Marble
Sc	Schist
Sh	Shale
sl/st	Siltstone
Sl	Slate
ss	Sandstone

SAMPLES

DS	Disturbed
UD	Undisturbed
Core NX Core	

KEY TO DRILL HOLE (DH) LOGS

0.0	Number of blows required for 1 ft. standard penetration, using 2.0" O.D. split barrel sampler, 140 lb hammer, and 30" drop. ASTM D 1586 (N)
22	Depth in hole (ft.)
CL	Unified Soil Classification Symbol
12.0	Dry barrel sampler
DBS	Roller bit to advance hole by wash
RH	Hole advanced by auger
AUG	
17.0	Rock core, 2-1/8" diameter
732	Percent rock core recovery in each drill run
90% LS	Bedrock symbol
24.0	
WL	Water Level

FOR IN-SERVICE USE ONLYNANTICOKE CREEK WATERSHEDSITE 10FLOODWATER RETARDING DAMBROOME COUNTY, NEW YORKLOGS OF TEST HOLESU. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

Date	7-69
Logger	Bruce Chang
Drawn	
Drawn	
Checked	F.I.
File No.	NY-2010-P

PC-31

## INTERVAL BOUNDARY DESCRIPTIONS

**A**

Gravel, sandy-wet (max. size 20"; est. 1% > 6", 15% 3-6", 70% matrix); approx. 40% gravel, 25% sand, 15% silt (fines); overwash material mostly sub-angular, flaggy siltsstones; silt fines, 15-20-27, PI= 30-73; gray to brown, depending on water tables; moist above, saturated below water level; rapid permeability, D=0.5-5 ft/d; dry easily, D= 30-75 (dense - very dense); irregularly laminated; alluvial, stream channel deposits; D.S. 303.1 (OC-GN), D.S. 301.1 (GN-GN).

**B**

Gravel, silty, clayey w/sand (max. size 24"; est. 7% > 6", 10% 3-6", 70% matrix); approx. 40% gravel, 30% sand, 10% fines); overwash material ranges from sub-angular, flaggy siltsstones to spherical varieties; silt or clay fines, 15-21-25, PI= 30-41; color varies from gray (Bg) to brown (BG), depending on moisture content; usually moist; essentially very slight permeability, D=0.5; D is never less than 22, usually > 40 (very stiff-hard); occasionally laminated or pseudo-stratified and often shows variation of 10% either side of norm.; glacial till: D.S.'s 202.1 (OC-GN), 211.1 (GN), 211.2 (GN), 201.1 (GN).

GC 6m

**C**

Silt and clay, gravelly w/sand (max. size 20"; est. 7% > 6", 15% 3-6", 70% matrix); approx. 25% gravel, 15% sand, 60% fines); overwash material varies same as B; silt and clay fines, 15-21-25, PI= 30-73; color varies same as B; usually moist; very slight permeability, D never less than 20, usually > 40 (very stiff-hard); occasionally laminated or pseudo-stratified and often shows variation of 10% either side of norm.; glacial till: D.S.'s 4.1 (CL-ML), 205.1 (CL-ML), 205.2 (ML), 209.1 (CL-ML), 209.2 (CL-ML), 223.1 (CL-ML), 224.1 (ML), 225.1 (CL-ML), 225.2 (CL-ML), 201.1 (CL-ML).

**D**

Silt, sandy (max. size 10mm; approx. 20% sand, 80% silt fines); non-plastic; brownish-musty-wet; moderate permeability; dries easily, D= 3-15 (medium to stiff); alluvial, overbank flood plain deposits with occasional organics; D.S.'s 301.1 and 303.1 (GN).

**E**

Silt and clay (max. size 1"; approx. 3% gravel, 3% sand, 9% fines); 15-23-32, PI= 3-9; usually gray, sometimes brown; moist; very slight permeability, D= 26-74 (hard); sometimes occurs as rhythmically graded beds; glacio-lacustrine; D.S.'s 203.1, 204.1, 221.1, 224.2 (all CL-ML).

**F**

Sand, silty (est. 60% sand, 40% fines) non-plastic, dilatant fines; brown; wet; moderate permeability; D= 23-50 (very stiff-hard); found in jar samples only; possibly glacio lacustrine; not both sampled (GN or GLT).

**G**

Silt, gravelly w/sand (max. size 10mm; est. 30% > 3", 70% matrix); approx. 25% gravel, 20% sand, 35% fines); overwash area flaggy shales and siltstones (locally derived); brown to yellow-brown; dry-moist; rapid permeability; loose medium; calcareous; found along steep right bank over bedrock; not both sampled (GN).

**H**

Topsoil; roots and organics; brown; moist; medium to rapid permeability; lenses; very rocky on steep right abutment; ave. thickness 1.5'.

**I**

Bedrock; silty shales and siltstones w/few fine sandstone beds; usually highly weathered (angulose) for 3', grading through badly fractured rock and into fresh unweathered rock; gray to medium to dark; mostly thin-bedded w/few 6" coarse beds of sandstone or fossiliferous (brachiopods) siltstones; fossils calcareous; few vertical joints in core; fractures vary w/ C-subs dips slightly to south; Baynes Op. - Catherline shale and Middlesex shale, lower Upper Devonian. (see core photos)

## TEST PIT LOGS

## TP #1, Centerline of Dam Elev. 1191.7, D.B.C. 4/3/69

0.0 - 0.6 Material H (Topsoil)  
0.6 13.0 Material Bb (GN)  
13.0 16.0 + Material Bg (GN)

Notes: Dry pit

## TP #2, Centerline of Dam Elev. 1102.9, D.B.C. 4/3/69

0.0 - 1.0 Material H (Topsoil)  
1.0 12.3 Material Bb (GN)  
12.3 16.0 + Material Bg (GN)

Notes: Dry pit

## TP #3, Centerline of Dam Elev. 1179.5, D.B.C. 4/3/69

0.0 1.3 Material H (Topsoil)  
1.3 3.0 Material G (ML litter)  
3.0 6.0 + Material I (sh & silt)

Notes: Water @ creek level. Topsoil rocky. Rock dips quite easily w/buckshot.

## TP #4, Centerline of Dam Elev. 1179.7, D.B.C. 4/3/69

0.0 1.3 Material H (Topsoil)  
1.3 17.0 Material Ch (CL-ML) DS 4.1 CL-ML  
17.0 + Material I (sh & silt)

Notes: Water at top of rock.

## TP #2a1, Left Emergency Spwy. Elev. 1161.4, D.B.C. 4/3/69

0.0 1.6 Material H (Topsoil)  
1.6 8.0 Material Ch (ML)  
8.0 16.0 + Material Cg (ML)

Notes: Dry pit.

## TP #2a2, Left Emergency Spwy. Elev. 1132.8, D.B.C. 4/3/69

0.0 1.3 Material H (Topsoil)  
1.3 6.0 Material Bb (GN)  
6.0 16.0 + Material Bg (GN) DS 202.1 OC-GN

Notes: Surface drainage kept first 2.0' wet. Rest is dry.

## TP #2a3, Left Emergency Spwy. Elev. 1170.1, D.B.C. 4/3/69

0.0 1.3 Material H (Topsoil)  
1.3 7.0 Material Ch (ML)  
7.0 16.0 Material Cg (ML)  
16.0 17.0 + Material E (CL) DS 203.1 CL-ML

Notes: Dry pit.

## TP #2a4, Left Emergency Spwy. Elev. 1177.8, D.B.C. 4/3/69

0.0 1.2 Material H (Topsoil)  
1.2 11.0 Material Ch (ML)  
11.0 13.0 Material Cg (ML)  
13.0 17.0 + Material E (CL-ML) DS 204.1 CL-ML

Notes: Dry pit. Material E "varved" or rhythmically bedded.

## TP #2a5, Left Emergency Spwy. Elev. 1161.6, D.B.C. 4/3/69

0.0 1.0 Material H (Topsoil)  
1.0 10.0 Material Ch (ML) DS 205.1 CL-ML  
10.0 18.0 Material Cg (ML) DS 205.2 CL-ML

Notes: Dry pit. No material E as such, but occasional pods and segregations of CL and ML in 10.0' - 18.0' zone.

## TP #2a6, Left Emergency Spwy. Elev. 1140.2, D.B.C. 4/3/69

0.0 1.5 Material H (Topsoil)  
1.5 14.0 Material Ch (ML)  
14.0 18.0 + Material Cg (ML)

Notes: Dry pit.

## TP #2a7, Left Emergency Spwy. Elev. 1123.6, D.B.C. 4/4/69

0.0 1.3 Material H (Topsoil)  
1.3 9.0 Material Bb (GN)  
9.0 17.7 Material Bg (GN)  
17.7 + Material I (sh & silt)

Notes: Small amount of water on top of rock. Could not rip rock, probably because near end of buckshot reach.

## TP #2a8, Left Emergency Spwy. Elev. 1141.7, D.B.C. 4/

0.0 1.0 Material H (Topsoil)  
1.0 9.0 Material Bb (GN)  
9.0 17.0 + Material Bg (GN)

Notes: Dry pit.

## TP #2a9, Left Emergency Spwy. Elev. 1183.3, D.B.C. 4/

0.0 1.5 Material H (Topsoil)  
1.5 13.0 Material Ch (ML) DS 209.1 CL-ML  
13.0 18.0 + Material Cg (ML) DS 209.2 CL-ML

Notes: Dry pit.

## TP #2a10, Left Emergency Spwy. Elev. 1164.8, D.B.C. 4/

0.0 1.5 Material H (Topsoil)  
1.5 8.0 Material Ch (ML)  
8.0 17.0 + Material Cg (ML)

Notes: Becomes wet @ ~ 8.0'.

## TP #2a11, Left Emergency Spwy. Elev. 1147.9, D.B.C. 4/

0.0 1.5 Material H (Topsoil)  
1.5 8.0 Material Bb (GN)  
8.0 17.0 + Material Bg (GN) DS 211.1 GN

Notes: Wet below 8.0'. Caved.

## TP #2a12, Left Emergency Spwy. Elev. 1130.5, D.B.C. 4/

0.0 1.3 Material H (Topsoil)  
1.3 9.0 Material Bb (GN)  
9.0 19.0 Material Bg (GN)  
19.0 + Material I (sh & silt)

Notes: Very wet and caved below 9.0'. Could not rip rock because of depth.

## TP #2a13 - 220. Not dug.

## TP #2a14, Right Emergency Spwy. Elev. 1150.9, A.H.C.

0.0 1.3 Material H (Topsoil)  
1.3 9.5 Material Ch (ML)  
9.5 10.0 + Material I (sh & silt) D.S.

Notes: Dry pit. Sandy silty lenses of Mat'l E 6.0' 6.5', D.S. 221.1, CL-ML. Top 1' of is quite gray when wet.

## TP #2a22, Right Emergency Spwy. Elev. 1137.4, A.H.C.

0.0 1.0 Material H (Topsoil)  
1.0 12.5 Material Ch (ML)

Notes: Dry pit. Top 2.5' of Ch is quite gray when wet.

## TP #2a23, Right Emergency Spwy. Elev. 1120.1, A.H.C.

0.0 0.5 Material H (Topsoil)  
0.5 11.5 Material Ch (ML)  
11.5 12.0 + Material Cg (ML) D.S. 223.1

Notes: Dry pit. Top 1' of Ch is quite gray when wet.

## TP #2a24, Right Emergency Spwy. Elev. 1130.2, A.H.C.

0.0 0.5 Material H (Topsoil)  
0.5 13.5 Material Ch (ML) D.S. 224.1

Notes: Dry pit. D.S. 224.1 runs about 10' from the bulk of Material C. Top 1' of Ch is gray.



**DAT**  
**FILM**